

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Tracy of Horizon Oil & Gas Co. has this
date requested permission to plug the following described well:

Mr. Tracy guarantees payment of the plugging fee.

Operator's full Name: Horizon Oil & Gas Company

Complete Address: Box 7, Spearman, Texas

Lease Name: Collingwood Well No. 1-21

Location: C E/2 SE Sec. 21 Twp. 32 Rge. 30 (E) (W)

County Meade Total Depth 6065' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Tracy was instructed to plug the well as follows:

8 5/8" to 1428' Circulated w/ cement. 4 1/2" to 6065' cemented.

Top Perforations 5955' Plug Bottom w/ 20 sacks cement.

Top of cement 5780' Mud 5780' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Very truly yours,

Edgar J. Eves
Conservation Division Agent