

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 191 - 10285 - 0000 (of this well)

Operator's Full Name TERRA Resources Inc.  
Complete Address P.O. Box 839 Oklahoma City, OK 73101  
Lease Name Wellington Unit Well No. # 115 - I  
Location NE NE SW Sec. 5 Twp. 32 S Rge. 1 (W)  
County Sumner Total Depth 3694'  
Abandoned Oil Well      Gas Well      Input Well X SWD Well      D & A       
Other well as hereafter indicated       
Plugging Contractor Same as Above  
Address      License No.       
Operation Completed: Hour 10:30 A.M. Day 13 Month 8 Year 1980

The above well was plugged as follows:

1 1/2" sur. cas 353' - exc/cent. - 6 5/8" cas 3644' left all cas. whole  
Sand plug 3453' / 5' sx cent., pushed plug 1 1/2" tub. 180'  
Rock bridge 170', pumped Flag down 6 5/8" cas, hole in cas. 60'  
ran 1" tub. between 6 5/8" & 1 1/2" cas 140', ran 2 1/2" tub. down 6 5/8" 140'  
Allied Cementing pumped 200' sx cent. down 1" to top of sur. pipe,  
pumped 25' sx cent. down 2 1/2" tub. to top of 6 5/8", pulled tub. 1" & 2 1/2" - 8-12-80  
8-13-80, cent. down 20' in 6 5/8, 53' between 6 5/8" & 1 1/2". Allied filled 6 5/8" / 5' sx cent.  
ran 1" to 53', Allied pumped 70' sx to top of sur. cas.

All cent. used was 50/50 posmix cent., 2 7/8 C.C., 2 7/8 L.C.M.  
I hereby certify that the above well was plugged as herein stated.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 19 1980  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: Don Thompson  
Well Plugging Supervisor