

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Ambassador Oil Corporation

Complete Address: 304 Hightower Bldg., Oklahoma City, Oklahoma

Lease Name Myer Well No. # 1

Location SE SW NE Sec. 23 Twp. 32 Rge. 30 (E) (W)W

County Meade Total Depth 6200

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Graham-Michaelis Drilling Company

Address: 211 N. Broadway, Wichita, Kansas License No. _____

Operation Completed: Hour 1:20AM Day 18th Month August Year 1964

The Above well was plugged as follows:

1617' of 8 5/8" surface pipe, cement circulated with 850 sacks. 1st cementing plug was pushed in fluid to 700', and cemented with 35 sacks, through the drill pipe, bringing the top of the cement to 580' in the surface pipe. Hole was filled with drilling mud to 40'. 2nd cementing plug, bridged with hulls, and cemented with 11 sacks to the base of the cellar. Rat and mouse hole was cemented with 14 sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

DATE 8/19/64

INV. NO. 9690-4

Signed: Archie Elving
Well Plugging Supervisor