

5-20

161
R

2-100599

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-191-22,155-0000
NE, SECTION 8 TOWNSHIP 30 RANGE 3W

OPERATOR LICENSE # 5063 3630 FEET FROM S SECTION LINE
660 FEET FROM E SECTION LINE

OPERATOR Energy Exploration, Inc.
NAME & 1002 South Broadway
ADDRESS Wichita, KS 67211

LEASE NAME: Emery #1
COUNTY: Sumner
WELL TOTAL DEPTH: 4340' - 141.05

CONDUCTOR PIPE: " @ "
SURFACE CASING: 8-5/8" @ 274'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD _____ D&A X
OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Lobo Drilling Company
ADDRESS: Box 877, Great Bend, KS 67530 LICENSE: 5864

COMPANY TO PLUG AT: HOUR: 1:00a DAY: 20 MONTH: 5 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: _____
COMPANY NAME: _____ PHONE: _____

WERE: 35 sx @ 1250' - 35 sx @ 330' - 25 sx @ 60'
mouse hole - 15 sx rat hole.

STATE CORPORATION COMMISSION
JUL 23 1990 7-23-90

PLUGGING PROPOSAL RECEIVED BY: Merlan Unruh

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (_____) NONE (X)

CONSERVATION DIVISION
Wichita, Kansas

COMPLETED: HOUR: 3:00a DAY: 20 MONTH: 5 YEAR: 1990

ACTUAL PLUGGING REPORT:

Filled hole w/mud - pulled drl pipe to 1250' &
spotted 35 sx cmt - pulled pipe to 330' & spotted 35 sx
cmt - at 60' circulated 25 sx to surface - put 15 sx
cmt in rat hole & 10 sx in mouse hole.

REMARKS: B. J. Titan #610760 60/40 3% gel

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE: 7-27-90

John Sanders
John Sanders (AGENT)

INV. NO. 28778