

7-16

299  
R

2-100610

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER: 15-191-22,065-0000

SE NW SE, SECTION 3 TOWNSHIP 30 RANGE 3W

OPERATOR LICENSE # 3667 FEET FROM S SECTION LINE \_\_\_\_\_  
FEET FROM E SECTION LINE \_\_\_\_\_

OPERATOR Source Petroleum  
NAME & ADDRESS 200 W. Douglas, #280  
Wichita, KS 67202

LEASE NAME: Little #A-1 142.68  
COUNTY: Sumner  
WELL TOTAL DEPTH: 4390' CIBP 3760'

CONDUCTOR PIPE: 4-1/2" @ 4377'/300 SX

SURFACE CASING: 8-5/8" @ 267'/180 SX

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SLD \_\_\_\_\_ D&A \_\_\_\_\_  
OTHER WELL AS HEREINAFTER INDICATED: Perf 3807-11' 3320-22' 3289-91'

PLUGGING CONTRACTOR: Clarke Corporation  
ADDRESS: Box 187, Medicine Lodge, KS 67104 LICENSE: 5105

COMPANY TO PLUG AT: HOUR: 9:00a DAY: 16 MONTH: 7 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Chuck Smith  
COMPANY NAME: Clarke Corporation PHONE: \_\_\_\_\_  
WERE: Sand from 3760' to 3230' - dump 4 sx cmt w/bailer -  
plug thru pipe coming up 816' 25 sx - 559' 25 sx - 303'  
circ to surface.

PLUGGING PROPOSAL RECEIVED BY: John Sanders  
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 12:00p DAY: 16 MONTH: 7 YEAR: 1990

ACTUAL PLUGGING REPORT:  
Sanded to 3230' & dumped 4 sx cmt w/bailer - shot &  
pulled 2100' of 4-1/2" to 816' - spotted 25 sx cmt  
pulled pipe to 559' & spotted 25 sx cmt - pulled pipe  
to 303' & circulated to surface.

REMARKS: B. J. Titan #610824

I DID OBSERVE THIS PLUGGING.

INVOICED

J. L. Sanders  
J. L. Sanders (AGENT)

DATE: 8-2-90

WELL NO. 28867

7-16

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
AUG 7 1990

7-31-90