

7-16

2-100610

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-191-22,065 - 0000

SE NW SE, SECTION 3 TOWNSHIP 30 RANGE 3W

OPERATOR LICENSE # 3667

FEET FROM S SECTION LINE

FEET FROM E SECTION LINE

OPERATOR Source Petroleum
NAME & 200 W. Douglas, #280
ADDRESS Wichita, KS 67202

LEASE NAME: Little #A-1
COUNTY: Sumner 142.67
WELL TOTAL DEPTH: 4390' CIBP 3760'

CONDUCTOR PIPE: 4-1/2" @ 4377'/300 SX

SURFACE CASING: 8-5/8" @ 267'/180 SX

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A
OTHER WELL AS HEREINAFTER INDICATED: Perf 3807-11' 3320-22' 3289-91'

PLUGGING CONTRACTOR: Clarke Corporation
ADDRESS: Box 187, Medicine Lodge, KS 67104 LICENSE: 5105

COMPANY TO PLUG AT: HOUR: 9:00a DAY: 16 MONTH: 7 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Chuck Smith
COMPANY NAME: Clarke Corporation PHONE: _____
WERE: Sand from 3760' to 3230' - dump 4 sx cmt w/bailer -
plug thru pipe coming up 816' 25 sx - 559' 25 sx - 303'
circ to surface.

PLUGGING PROPOSAL RECEIVED BY: John Sanders
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 12:00p DAY: 16 MONTH: 7 YEAR: 1990

ACTUAL PLUGGING REPORT:
Sanded to 3230' & dumped 4 sx cmt w/bailer - shot &
pulled 2100' of 4-1/2" to 816' - spotted 25 sx cmt -
pulled pipe to 559' & spotted 25 sx cmt - pulled pipe
to 303' & circulated to surface.

REMARKS: B. J. Titan #610824

I DID OBSERVE THIS PLUGGING.
STATE CORPORATION COMMISSION

AUG - 17 1990
J. L. Sanders
CONSERVATION DIVISION, L. Sanders (AGENT)
Wichita, Kansas

INVOICED

DATE: 8-24-90

INV. NO. 29054

FORM CP-2/3
REV. 3/90