

11-10-89

2-040548

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 191-22,136 - 0000

SW, SECTION 3 TOWNSHIP 30 RANGE 3W

OPERATOR LICENSE # 4569 1650 FEET FROM S SECTION LINE
2970 FEET FROM E SECTION LINE

OPERATOR Jay Boy Oil Company
NAME & 224 E. Douglas, #425
ADDRESS Wichita, KS 67202

LEASE NAME: Stinson #1
COUNTY: Sumner
WELL TOTAL DEPTH: 3886' - 126.30
CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 261'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A X
OTHER WELL AS HEREINAFTER INDICATED: _____
PLUGGING CONTRACTOR: Tornado Drilling

ADDRESS: Canton, KS LICENSE: 3890

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Brian Galley
COMPANY NAME: Tornado Drilling PHONE: _____
WERE: 35 sx @ 600' - 35 sx @ 300' - 25 sx @ 60' - 10 sx in
RH - 5 sx WW

PLUGGING PROPOSAL RECEIVED BY: District #2
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 08:30 DAY: 10 MONTH: 11 YEAR: 1989

ACTUAL PLUGGING REPORT:
Drl pipe was run in open-ended to 600' where 35 sx of
cmt spotted in place - drl pipe pulled to 300' & 35 sx
cmt spotted - drl pipe pulled to 60' & cmt circ to
surface - rat hole circ w/10 sx cmt - WW plugged w/5 sx
cmt

REMARKS: Howco #878764-7 60/40 2% gel

I DID NOT OBSERVE THIS PLUGGING.

RECEIVED
STATE CORPORATION COMMISSION

Steve Van Gieson (AGENT)

INVOICED AUG 15 1990

DATE: 8-17-90 CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 29001
11-10-89 SEP 14 1990

FORM CP-2/3
REV. 3/90