

2 100450

11-15-173-71818-0000
15-173-03846-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 11/19/63

SE NE, SEC. 28, T 29 S, R 1 W/EX

feet from S section line

feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Gillian Unit Well # 4

Operator: Gear Petro Co. Inc.
Name & Address 1075 KSB Bldg. - 125 N. Market
Wichita, KS 67202
316-265-3351

County Sedgwick 121.16

Well Total Depth 3728 feet

Conductor Pipe: Size 4-1/2 feet 3721

Surface Casing: Size 8-5/8 feet 355

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated Perf 3721'-28'

Plugging Contractor Butler County Drlg License Number 4421

Address 332 State Bank Bldg Winfield, KS 67156

Company to plug at: Hour: 2:00p Day: 31 Month: 10 Year: 1988

Plugging proposal received from Jim Thatcher

(company name) Gear Petro (phone)

were: Sand to 3670' & dump 5 sx cement - shoot & pull pipe - no pipe pulled - shoot
hole at 400' & circulate to surface in and outside 4-1/2"

RECEIVED
STATE CORPORATION COMMISSION

JAN 04 1989

Plugging Proposal Received by

CONSERVATION DIVISION
Snyder
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☐ Part ☐ None ☒

Operations Completed: Hour: 4:00p Day: 1 Month: 11 Year: 1988

ACTUAL PLUGGING REPORT Sanded bottom to 3670' & dumped 5 sx cement - set bridge at
400' inside 4-1/2" - run 1" & circulate between 8-5/8" and 4-1/2" & circulated inside
4-1/2" to surface - pull 1" & welded cap on top.

Remarks: Allied Cementing

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-9-89 observe this plugging.

Signed Johnny C Sanders
(TECHNICIAN)

INV. NO. 23550

FORM CP-2/3
Rev. 01-84