

15-173-01202-0000
11-27 2-051049

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: D & C 1964
C NW SW, SECTION 27 TOWNSHIP 29 RANGE 1W

OPERATOR LICENSE # 5151 1980 FEET FROM S SECTION LINE
4620 FEET FROM E SECTION LINE

OPERATOR Gear Petroleum Co., Inc.
NAME & 125 North Market
ADDRESS Wichita, KS 67202

LEASE NAME: Gillian/Little #5

COUNTY: Sedgwick

WELL TOTAL DEPTH: 3810' 123.82

CONDUCTOR PIPE: " @ '

SURFACE CASING: 8-5/8" @ 296'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Gressel
ADDRESS: _____ LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: 26 MONTH: 11 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: _____

COMPANY NAME: _____ PHONE: _____

WERE: 5-1/2" set @ 3809' w/125 sx cmt & perf @ 3748-58' -
sand back to 3700' & pump 5 sx cmt - circ cmt from 450'
to surface.

PLUGGING PROPOSAL RECEIVED BY: Glenn Ward

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 12:30p DAY: 27 MONTH: 11 YEAR: 1990

ACTUAL PLUGGING REPORT:
Sanded back to 3700' & dumped 5 sx cmt w/dump bailer -
perf 5-1/2" csg @ 450' & circ cmt inside & outside of
5-1/2" to surface.

REMARKS: Allied 60/40 poz

I DID OBSERVE THIS PLUGGING.

INVOICED

Glenn Ward
Glenn Ward (AGENT)

DATE 12-14-90

INV. NO. 30261