

15-173-01632-0000

5-20

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 27 1994

CONSERVATION DIVISION
WICHITA, KS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

5-27-94

API NUMBER: 6/23/64
NW SW NE, SECTION 15 TOWNSHIP 29 RANGE 1W

OPERATOR LICENSE # 6679 3630 FEET FROM S SECTION LINE
2310 FEET FROM E SECTION LINE

OPERATOR W D SHORT
NAME & P O BOX 1
ADDRESS OXFORD KS 67119

LEASE NAME: OSA UNIT #13
COUNTY: SEDGWICK
WELL TOTAL DEPTH: 3763' 122.29

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 316'/300 SX

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: 5-1/2" @ 3753'/125 SX - PERFS 3379-90'

PLUGGING CONTRACTOR: W D SHORT
ADDRESS: _____ LICENSE: 6679

COMPANY TO PLUG AT: HOUR: _____ DAY: 20 MONTH: 5 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: W D SHORT

COMPANY NAME: _____ PHONE: _____

WERE: _____

PLUGGING PROPOSAL RECEIVED BY: MIKE WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART () NONE (_____)

COMPLETED: HOUR: _____ DAY: 20 MONTH: 5 YEAR: 1994

ACTUAL PLUGGING REPORT:
SAND BACK TO 3713' - CAP W/5 SX CMT - MISSISSIPPI WAS
PERFED FROM 3379-90' - 10 SX PUMPED TO SQUEEZE OFF
MISS. - 5-1/2" SHOT OFF @ 2332' & PULLED FROM WELL BORE
- 2" TUB RUN TO 360' - 5 YDS SLURRY DUMPED - CMT DID
NOT CIRC - TAGGED CMT @ 137' - DUMPED APPROX 2 YDS
SLURRY WHICH CIRC TO SURF

REMARKS: DOLESE REDIMIX #06966 & #67012

I DID OBSERVE THIS PLUGGING.

INVOICED
DATE 6-1-94
INV. NO. 40519

Dave Wertz
Dave Wertz (AGENT)