


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WASH DOWN
WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Sedgwick

County. Sec. 28 Twp. 29 Rge. 1 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner Shawver Armour, Inc.

Lease Name TOURBIER (WASH DOWN) Well No. 2

Office Address 817 Central Building, Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Feb. 27th 1964

Application for plugging filed Feb. 27th 1964

Application for plugging approved Feb. 27th 1964

Plugging commenced Feb. 27th 1964

Plugging completed Feb. 27th 1964

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin

Producing formation Depth to top Bottom Total Depth of Well 3940 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
WASH DOWN						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole with 44 Vis. mud to 200'
Set a dry hole plug
Added 1/2 sacks hulls & 15 sacks cement
Mudded hole from this point to 40'
Set dry hole plug added 1/4 sack hulls
& 8 sacks cement
Capped rat hole w/2 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

MAR 5 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shawver Armour, Inc.
Address 817 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
James M. Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Armour
James M. Armour, 817 Central Bldg.,
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 1964

My commission expires Dec 10, 1967

Claire Jones Notary Public.

15-173-00177-0001

(Handwritten mark)

D R I L L E R ' S L O G

WASH DOWN

FARM NAME: TOURBIER # 2 LOCATION: NW NW SE Sec. 28-29-1W
CONTRACTOR: SHAWVER ARMOUR, INC. Sedgwick County, Kansas
OWNER: SHAWVER ARMOUR, INC. ELEVATION: 1268 KB
COMMENCED: February 22, 1964 COMPLETED: February 27, 1964

FORMATION:		TOPS	
Washed down	3478	Mississippian	3515
Shale & Lime	3517	Kinderhook	3857
Mississippian Lime	3552	Simpson Sand	3915
Lime	3858		
Kinderhook	3915		
Simpson Sand	3940		
Rotary Total Depth	3940		

STATE OF KANSAS }
SEDGWICK COUNTY } ss

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1964
CONSERVATION DIVISION
Wichita, Kansas

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

BY James M. Armour
James M. Armour

Subscribed and sworn to before me this 3rd day of March, 1964.

Claire Jones
Claire Jones, Notary Public

My commission expires December 10, 1967.