


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sedgwick County, Sec. 28 Twp. 29S Rge. 1 (W)
Location as "NE/CNW/SW" or footage from lines NE SW SE
Lease Owner Shawver Armour, Inc.
Lease Name Tourbier Well No. 1
Office Address 817 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 21, 1964
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 19____
Plugging completed _____ 19____
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3780 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface	water	-0-	312'	8 5/8"	312	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole to 225' w/47 Vis mud.
Set a dry hole plug added 1/2 sax hul\$s and 15 sx cement
Mudded hole from this point to 30'
Set a plug - Added 1/4 sax hulls & 8 sxs cement
Filled rat hole to within 8' of surface w/mud & dumped
2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 3 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver Armour, Inc.
Address 817 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
James M. Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Armour
James M. Armour, 817 Central Bldg.,
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 28th day of February, 19 64.

My commission expires December 10, 1967 Claire Jones Notary Public.

R

DRILLER'S LOG

FARM NAME: TOURBIER # 1 LOCATION: NE ^{SE} ~~SW~~ Sec. 28-29S-1W
 OWNER: SHAWVER ARMOUR, INC. Sedgwick County, Ks
 CONTRACTOR: SHAWVER ARMOUR, INC. ELEVATION: 1263 KB
 COMMENCED: February 8, 1964 COMPLETED: February 21, 1964
 CASING RECORD: 312' 8 5/8" 1st time w/350 sx cement & 9 sx cc
 washed down outside & one inched it w/164 sx cement
 and 3 sx cc

FORMATION:

Anhydrite 480
 Shale & Lime 670
 Lime & Shale 930
 Shale & Lime 1495
 Lime & Shale 1640
 Shale & Lime 2135
 Lime & Shale 2390
 Shale 2504
 Stalnaker Sand 2585
 Sand & Shale 2624
 Shale & Lime 2822
 Lime 3029
 Lime & Shale 3276
 Shale & Lime 3361
 Lime 3366
 Lime & Shale 3381
 Lime 3690
 Shale 3727
 Simpson 3780

TOPS:

Stalnaker 2504
 Kansas City 2822
 Base Kansas City 3029
 Mississippian 3381
 Kinderhook 3665
 Simpson 3727

Rotary Total Depth 3780

RECEIVED
 STATE CORPORATION COMMISSION

MAR 3 1964

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 SEDGWICK COUNTY) ss

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

By James M. Armour
 James M. Armour

Subscribed and sworn to before me this
 28th day of February, 1964.

My commission expires Dec. 10th, 1967

Claire Jones
 Claire Jones, Notary Public