

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County. Sec. 28 Twp. 29 Rge. ~~(E)~~ 1 (W)
Location as "NE/CNW/SW" or footage from lines Cen. NE NE
Lease Owner E. H. Adair Oil Co.
Lease Name Schmeissner Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 8-9-63 19
Application for plugging filed 9-28-66 9/6/66 19
Application for plugging approved 9-21-66 9/6/66 19
Plugging commenced 9-21-66 9/6/66 19
Plugging completed 9-21-66 9/6/66 19
Reason for abandonment of well or producing formation Well made too much water.

If a producing well is abandoned, date of last production August 1966 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation Simpson Sand Depth to top 3742 Bottom 3760 Total Depth of Well 3760 Feet
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Copy of Drillers Log attached hereto.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set a fifteen foot rock bridge from 240 feet to 225 feet. Added twenty sacks of cement. Set a ten foot rock bridge at 40 feet. Added ten sacks of cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1966
9-29-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E. H. Adair Oil Co.
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Sherrill Compton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Sherrill Compton
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of September, 1966

My commission expires 4-23-68

Frances D. Eubanks
Frances D. Eubanks Notary Public.



E. H. Adair Oil Company
1005 East Second Street
Wichita, Kansas

E. H. Adair Oil Company, et al,
Schmeissner - No. 1
C - NE NE of
Sec. 28-Twp. 29S-Rge. 1W.,
Sedgwick County, Kansas

Elevation: 1,272 K.B.

Comm: 7-25-63
Comp: 8-9-63
Contractor:
E. H. Adair
8-5/8 in. s/csg, @ 350 ft.
w/650 sax.
5-1/2 in. @ 3,744 ft.
w/50 sax.

Figures indicate bottoms of formations:

Shlae and lime	to	2400	Shale	to	3127
Shale		2532	Lime & shaley lime		3348
Lime		2541	Shale		3388
Sand		2657	Lime & cherty lime		3659
Shale		2682	Shale		3670
Lime		2708	Lime		3686
Shale		2850	Shale		3742
Lime		3051	Sand, show oil		3757
Shale		3096	Shale		3760
Lime		3102	R.T.D.		3760

Tops:

IATAN LIMESTONE	2532	(-1260)
STALNAKER SAND	2541	(-1269)
KANSAS CITY	2850	(-1578)
BASE KANSAS CITY	3051	(-1779)
MISSISSIPPI LIMESTONE	3388	(-2116)
KINDERHOOK SHALE	3686	(-2414)
SIMPSON SAND	3742	(-2470)

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1966

CONSERVATION DIVISION
Wichita, Kansas

Certified correct:

Sherrill Compton
Sherrill Compton - Geologist