

15-173-03846-00-00

173-71818-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 11/19/63LEASE NAME Gillian UnitWELL NUMBER 4SPOT LOCATION SE NESEC. 28 TWP. 29 RGE. 1 WCOUNTY SedgwickDate Well Completed 11/19/63Plugging Commenced 10-31-88Plugging Completed 11-1-88

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Geason Petroleum Co., Inc.ADDRESS 1075 KSB Bldg 125 N. Market Wichita, KSPHONE (316) 265-3351 OPERATORS LICENSE NO. 5151Character of Well Input(Oil, Gas, D&A, SWD, Input, Water Supply Well)Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YesWhich KCC/KDHE Joint Office did you notify? Wichita, KSIs ACO-1 filed? no If not, is well log attached? YES filed with application to plugProducing formation Mississippi Depth to top 3721 bottom 3728 T.O. 3728

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-------------|---------|------|----|-------|--------|------------|
| Mississippi | oil | 3721 | 28 | 8 5/8 | 355 | none |
| | | | | 4 1/2 | 3721 | none |
| | | | | | | |
| | | | | | | |


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Sanded bottom off from 3728' to 3670'- bailer dumped 5 sacks cement on bottom. Set bridge in 4 1/2-400' from surface run 1" between 8 5/8 and 4 1/2 to 400' below surface and circulated cement to surface. Pulled 1" out welded plate on top.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Butler County Drilling License No. 4421Address 332 State Bank Bldg.
Winfield, KS 67156STATE OF KANSAS COUNTY OF SEDGWICK, ss.Jim Thatcher

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim Thatcher(Address) 1075 KSB Bldg. 125 N. Market
Wichita, KS 67202SUBSCRIBED AND SWORN TO before me this 11 day of November, 19 88My Commission expires: 8/1/89Pauletta K. Engels
Notary Public

H. M. Adair Oil Company
1005 East Second Street
Wichita 14, Kansas.

GILLIAN UNIT #4

H. M. Adair Oil Company, and
Ray Whorton
SCHEISSNER "B" - No. 1
130 ft. SE of Center of
SE/4 of NE/4 of
Sec. 28-Twp. 29S-Rge. 1 W.,
Sedgwick County, Kansas.

Elevation: 1,272 K.B.

Comm.: 11-9-63
Comp.: 11-19-63
Contractor:
Adair - Rig No. 3
8-5/8 in. p/csg. @ 355ft.
w/300 sax.
4-1/2 in. @ 3,721 ft.
w/75 sax.

Figures indicate bottom of formations:

| | | | | |
|-------------------|------|--------|----|------|
| Shale and lime to | 2400 | Shale | to | 3114 |
| Shale | 2509 | Lime | | 3334 |
| Lime | 2518 | Shale | | 3368 |
| Sand and shale | 2534 | Lime | | 3375 |
| Shale | 2587 | Shale- | | 3392 |
| Sand | 2698 | Lime | | 3658 |
| Shale | 2830 | Shale | | 3719 |
| Lime | 3035 | Sand | | 3728 |
| Shale | 3081 | R.T.D. | | 3728 |
| Lime | 3091 | | | |

Sample Tops:

| | |
|------------------|--------------|
| IATAN | 2509 (-1237) |
| STALMAKER | 2518 (-1246) |
| KANSAS CITY | 2830 (-1558) |
| EAST KANSAS CITY | 3035 (-1763) |
| MISSISSIPPI | 3392 (-2120) |
| KINDERHOOK | 3658 (-2386) |
| SIMPSON SAND | 3719 (-2447) |
| R.T.D. | 3728 |

RECEIVED
STATE CORPORATION COMMISSION

OCT 4 1968

CONSERVATION DIVISION
Wichita, Kansas

Certified correct:

Sherrill Compton
Sherrill Compton - Geologist.