

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-173-20068-0000

LEASE NAME Gillian Unit

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

4514 Ft. from S Section Line

3406 Ft. from E Section Line

SEC. 27 TWP. 29 RGE. 1 (E or W)

COUNTY Sedgwick

LEASE OPERATOR Gear Petroleum Co., Inc.

ADDRESS 125 N. Market #1075 Wichita, KS 67202

PHONE# (316) 265-3351 OPERATORS LICENSE NO. 5151

Date Well Completed 12/30/90

Character of Well Water Supply Well

Plugging Commenced 11/26/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/27/90

The plugging proposal was approved on 11/21/90 (date)

by Dave Wertz (KCC District Agent's Name).

Is ACO-1 filed? * If not, Is well log attached? Sent with plugging application.

Producing Formation * Drilled prior to ACO-1 requirement. Stalnaker Depth to Top 2591 Bottom 2631 T.D. 3837

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Simpson	Water	3752	3758	8 5/8	372	NONE
Stalnaker	Water	2591	2631	5 1/2	3836	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Cast iron bridge plug at 2750 with 1 sx cement on top. Sand back to 2540, dump 5 sx cement. Perf at 450 and circulate 175 sx 60/40 poz 2% gel. Down casing up backside to surface. Shut in pressure 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gear Petroleum Co., Inc. License No. 5151

Address 125 N. Market #1075 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gear Petroleum Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jim Thatcher (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
12-5-90 DEC 5 1990

(Signature) Jim Thatcher
125 N. Market #1074
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 4th day of December, 19 90

POLLY TILTON
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 8-1-92

Polly Tilton
Notary Public

Commission Expires: 8-1-93

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

G. H. LUCKNER #3
766' FNL & 1874' FWL Section 27-29S-1W
Sedgwick County, Kansas

Commenced: December 16, 1970
Completed: December 30, 1970

OPERATOR - Continental Oil Company

DEPTH		FORMATION	REMARKS
From	To		
0	40	Top soil and clay	
40	255	Shale	
255	376	Shale, lime and shells	Ran 11 joints of 8-5/8" casing set @ 372' w/250 sacks cement.
376	1705	Shale and lime	
1705	2509	Lime and shale	
2509	2570	Sand and shale	
2570	2735	Shale	
2735	3286	Lime and shale	
3286	3755	Lime	
3755	3799	Core (Simpson)	
3799	3837	Sand and shale	
3837	TD		Ran 116 joints 5-1/2" casing set @ 3836 w/350 sacks cement.

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Well Log for the well drilled 766' FNL and 1874' FWL Section 27-29S-1W, Sedgwick County, Kansas, to the best of my knowledge and belief.

James S. Sutton, II
James S. Sutton, II

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

OCT 8 1970

CORPORATION DIVISION
Wichita, Kansas

Before me, the undersigned, a Notary Public within and for said County and State, on this 8th day of January, 1971, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Barbara J. Layton
Barbara J. Layton, Notary Public

My Commission Expires February 1, 1972.

