

15-173-01203-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Gillian Unit

WELL NUMBER #1

4950 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 27 TWP. 29 RGE. 1 (X) or (W)

COUNTY Sedgwick

Date Well Completed 12/19/63

Plugging Commenced 5/11/87

Plugging Completed 5/12/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gear Petroleum Co., Inc.

ADDRESS 300 Sutton Place

PHONE#(316) 265-3351 OPERATORS LICENSE NO. 5151

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist #2

Is ACO-1 filed? NO If not, is well log attached? Yes

Producing Formation Simpson Depth to Top 3760 Bottom 3752 T.D. 3760

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Simpson				8 5/8	307	NONE
				5 1/2	3760	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 5/11/87 Sanded off bottom from 3755' to 3620'=135'. Plugged bottom w/5 SKS of Cem. & dump bailer. Ran 1" on outside fo 5 1/2" to 360'. SOIN. 5/12/87 Built bridge inside of 5 1/2", from 380' to 355'. United Cementing plugged outside of 5 1/2" w/60 SKS of 60/40 Poz-mix, & 3% Gel. Ran 1" inside of 5 1/2 to 355' & cemented to surface w/40 SKS of 60/40 Poz-mix, & 3% Gel. Job complete ...
(If additional description is necessary, use BACK of this form.) Cont. on back.

Name of Plugging Contractor Gear Petroleum Co., Inc. License No. 5151

Address 300 Sutton Place Wichita, KS 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Bob Gilpin (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert A. Gilpin

(Address) 300 Sutton Place Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 87

My Commission Expires: 8/1/89

PAULETTA K. ENGELS
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 8-1-89

RECEIVED
STATE CORPORATION COMMISSION

MAY 20 1987

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 07-86

INTER-ORGANIZATION CORRESPONDENCE

TO : E. B. Donnelly

DATE: December 30, 1963

FROM: Arden Ratzlaff

RE : Shawver-Armour & Lario Oil & Gas Company
 #1 Luckner
 C NW NW, Section 27-29-1W
 Sedgwick County, Kansas

Submitted herewith is the geological report on the captioned well.

One foot drilling time was kept from 2400' to 3752', rotary total depth.

Five foot samples were taken from 2400' to rotary total depth, except for the interval from 3000' to 3300' where ten foot samples were taken at the geologist's request.

The well was under geologic supervision from 2480' to 2530'; 2750' to 2975'; 3340' to 3420'; 3640' to 3752', rotary total depth.

Tabulated below are the formation tops as determined by sample examination. All measurements are from the kelly bushing elevation:

Elevation	1256' Gr.
	1261' K.B.
Brown Lime	2505' (-1244')
Stalnaker	2510' (-1249')
Kansas City	2814' (-1553')
Base Kansas City	3027' (-1766')
Mississippian	3383' (-2122')
Kinderhook	3693' (-2432')
Simpson	3749' (-2488')
Rotary Total Depth	3752' (-2491')

The well was under the geologic supervision of Denny Furst through the zones of interest in the Kansas City. He reported no shows above the Kansas City and the small shows of oil which he observed in the Kansas City have been condemned by drill stem tests in higher wells and are considered to be non-commercial. His description of these zones is described on the enclosed sample log.

No shows were observed in the Mississippian.

RECEIVED
 STATE CORPORATION COMMISSION

APR 21 1987

CONSERVATION DIVISION
 Wichita, Kansas