

15-173-01202-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 4/64
LEASE NAME Gillian Unit
WELL NUMBER 5

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from S Section Line
4620 Ft. from E Section Line
SEC. 27 TWP. 29 RGE. 1 ~~(XX)~~ or (W)
COUNTY Sedgwick
Date Well Completed 12/24/63
Plugging Commenced 11/26/90
Plugging Completed 11/27/90

LEASE OPERATOR Gear Petroleum Co., Inc.

ADDRESS 125 N. Market #1075 Wichita, KS 67202

PHONE#(316 265-3351 OPERATORS LICENSE NO. 5151

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/21/90 (date)

by Dave Wertz (KCC District Agent's Name).

Is ACO-1 filed? * If not, is well log attached? Sent with plugging application

*Drilled prior to ACO-1 requirement.

Producing Formation Simpson Depth to Top 3748 Bottom 3758 T.D. 3810

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Simpson</u>	<u>Oil</u>	<u>3748</u>	<u>58</u>	<u>8 5/8</u>	<u>296</u>	<u>NONE</u>
				<u>5 1/2</u>	<u>3809</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plug back with sant to 3698. Dump 5 sx cement. Perforate at 450 and circulate
175 sx 60/40 poz 2% gel down casing up backside to surface. Shut in pressure 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gear Petroleum Co., Inc. License No. 5151

Address 125 N. Market, #1075 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gear Petroleum Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jim Thatcher

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn and Bath, says: That I have knowledge of the facts, statements, and matters herein contained and of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas

DEC 5 1990

(Signature) Jim Thatcher

(Address) 125 N. Market #1075
Wichita, KS 67202

SUBSCRIBED AND SWORN TO Wichita, Kansas this 4 day of December, 1990

Polly Tilton
Notary Public

Commission Expires: 8/1/93



15-173-01202-0000
COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- RICK ISLAND REFINING CO.
Farm- Little No. 2
GILLIAN UNIT #5

SEC. 27 T. 29 R. 1W
C NW SW

Total Depth. 3810'
Comm. 12-10-63 Comp. 12-24-63
Shot or Treated.
Contractor. Gabbert-Jones, Inc.
Issued. 5-29-65

County Sedgwick
KANSAS



Elevation. 1278' KB

Production. Flow 383 BOPD

CASING:

8 5/8" 296' w/250 sx cem.
5 1/2" 3809' w/125 sx cem.

Figures Indicate Bottom of Formations.

surface soil, sand 82
shale, shells 430
shale 680
shale, lime 1485
lime 2895
lime, Kansas City 2960
lime 3025
lime, shale 3295
shale, lime 3400
lime, Mississippi 3435
Mississippi 3645
lime, shale 3750
Simpson 3752
Total Depth

TOPS: SCOUT
Iatan 2500
Stalnaker 2505
Lansing 2827
Mississippi 3379
Kinderhook 3691
Simpson 3746

K. G. S. LIBRARY