

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sedgwick County. Sec. 24 Twp. 29-S Rge. 1-N (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW NE

Lease Owner George P. Vye

Lease Name Callaway Well No. 2

Office Address 1006 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 7 1957

Application for plugging filed June 7 1957

Application for plugging approved June 7 1957


Plugging commenced June 7 1957

Plugging completed June 7 1957

Reason for abandonment of well or producing formation no oil in commercial quantities found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well S. S. Greider

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3375 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	286.57'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth (3375') to 250'. Set Plug #1 and 15 sacks cement to 205'. Filled hole with extra heavy rotary mud from 205' to 35'. Set Plug #2 and 10 sacks cement. Welded steel plate on surface pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Capitt Drilling, Inc.

Address 814 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss. R. R. McNicol (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol
814 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of June, 19 57

My commission expires September 30, 1959

Darlene May
Darlene May
Notary Public.

PLUGGING
FILE SEC 24 T 29 R 1W
BOOK PAGE 18 LINE 33

CONSERVATION

6-12-57

ROTARY DRILLING LOG

OPERATOR: George P. Vye
 Calloway #2
 NE NW NE Sec. 24-29S-1W
 Sedgwich County, Kansas

CONTRACTOR: Capitt Drilling Inc.
 COMM: 5-28-57
 COMP: 6-7-57

Formations:

Sand	80'
Shale	130'
Shale & Lime	287'
Shale	295'
Lime	445'
Shale	505'
Shale & Lime Strks.	785'
Shale & Lime	1004'
Sandy Shale & Lime Strks.	1638'
Shale & Lime	1750'
Shale & Lime Shells	1910'
Lime & Shale Brks.	2090'
Lime	2175'
Shale & Shells	2330'
Shale & Lime	2433'
Sandy Shale	2555'
Shale & Shells	2760'
Shale	2761'
Lime	2982'
Lime & Shale Brks.	3099'
Lime & Shale	3218'
Shale	3253'
Shale & Lime	3318'
Lime	3322'
Core #1	3330'
Core #2	3340'
Core #3	3356'
Core #4	3364'
Core #5	3375'
Rotary Total Depth	3375'

Remarks: Set 8-5/8" surface casing
 at 286.57' cemented with 200 sacks
 of common cement, 2% C.C.

We certify the above log is true
 and correct to the best of our
 knowledge and belief.

CAPITT DRILLING INC.

R.R. McNicol

R. R. McNicol

2

PLUGGING
FILE SEC 24 T 29 R 1W
BOOK PAGE 10 LINE 33

RECEIVED
 STATE CORPORATION COMMISSION

JUN 12 1957

CONSERVATION DIVISION
 Wichita