


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Sedgwick County. Sec. 22 Twp. 29 Rge. 1 NE
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE/NW/NE

Lease Owner Continental Oil Company
Lease Name O.S.A. UNIT Well No. 26
Office Address Box 267, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced June 14 1977
Plugging completed June 28 1977
Reason for abandonment of well or producing formation
depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3739'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	357'	none
				5 1/2"	3721'	2,479.57'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Dumped 3 sacks cement at 3680'.

Shot pipe at 3000', 2700' and 2500'.

Pulled a total of 75 joints of 5 1/2" casing.

Sun Cementing squeezed well with 3 sacks hulls, 15 sacks ~~gel~~ and

100 sacks cement with 4% added gel.


RECEIVED
STATE CORPORATION COMMISSION
JUL 05 1977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.
P. O. Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.



(Signature)

Box 698, Great Bend, Kansas 67530

(Address)

Subscribed AND SWORN TO before me this 1st day of July 1977

My commission expires May 21, 1980

Marla K. Haslam

Notary Public.

DIX #2

Casing Record: Company: Aylward Drilling Company Location: NE NW NE
Contractor: Aylward Drilling Company Sedgwick County
Kansas
8 5/8" - 357'
5 1/2" - 3721'
Commenced: May 7, 1964 Elevation: 1279 D.F.
Completed: May 15, 1964 1282 R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	35	Set 8 5/8" surface pipe @ 357' w/300
Sand	35	65	sacks cement.
Shale	65	225	
Lime	225	560	Geological Tops:
Red Bed	560	575	
Lime & Shale	575	2845	Stalnaker 2453
Lime	2845	3034	Kansas City 2788
Lime & Shale	3034	3352	Base Kansas City 2996
Lime	3352	3720	Mississippi 3352
Sand	3720	3739 T.D.	Kinderhook 3658
			Simpson 3720

DST 3718-39 Open 70" GTS 12" TSTM
Flowed oil in 43", reversed out
full string of oil
IBHP 1192#/30" - FBHP 1165#/30"
FP 108#-925#

Set 5 1/2" casing @ 3721' w/75 sacks.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Charles D. Williams

Subscribed and sworn to before me this 28th day of May, 1964

Duane Jessup
DUANE JESSUP Notary Public

My commission expires December 11, 1965

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1977
CONSERVATION DIVISION
Wichita, Kansas