


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sedgwick County, Sec. 22 Twp. 29 Rge. 1 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. 30' East of SW SW SE
Lease Owner Beardmore Drilling Company
Lease Name Casner Well No. 1
Office Address 827 Beacon Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-24 1957
Application for plugging filed 3-24 1957
Application for plugging approved 3-24 1957
Plugging commenced 3-24 1957
Plugging completed 3-24 1957
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3863 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand		0	65'			
Shale & Shells		65'	308'	8-5/8"	308'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

0 to 30' - 5 Sacks Cement

30' - Wood Plug

30' to 155' - Heavy Mud

155' to 200' - 15 Sacks Cement

200' - Wood Plug

200' to 3863' - Heavy Mud

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1957

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Company
Address 827 Beacon Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Heber Beardmore (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BEARDMORE DRILLING COMPANY

(Signature) By [Signature]
827 Beacon Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of March, 1957

My commission expires January 28, 1960

Leonard P. Tolle
Leonard P. Tolle - Notary Public.

PLUGGING
FILE SEC 22 T. 29 R. 1W
BOOK PAGE 1 LI. 43

BEARDMORE-SUTTON

#1 Casner
30th East of SW SW SE Sec. 22-29S-1W
Sedgwick County, Kansas

Drilled By: Beardmore Drilling Co.
Drilling Commenced: 3-13-57
Drilling Completed: 3-24-57

Casing Record:

8-5/8" set at 308^{ft} with 250 sacks cement on 3-13-57. Cement circulated.

Elevation: 1263 KB
1260 DF
1257 Gr

<u>FORMATIONS</u>	<u>DEPTH</u>
Cellar	5
Sand	65
Shale and Shells	250
Shale and Shells	308
Shale and Lime	375
Shale and Lime	1000
Shale and Lime	2100
Shale and Lime	2553
Sand	2628
Shale and Lime	2655
Shale and Lime	3020
Shale and Lime	3275
Shale and Lime	3345
Lime	3360
Shale and Lime	3430
Shale and Lime	3544
Shale and Lime	3739
Sand and Lime	3748
Sand	3759
Shale and Lime	3769
Lime	3863
Rotary Total Depth	3863

TOPS

Stalnaker	2496
Kansas City	2808
Mississippi	3371
Simpson Sand	3739
Arbuckle	3813

DST #1 - 3376-3390 Shut in 15 min., open 1 hr., shut in 15 min., recovered 70^{ft} muddy water. IF 30, FF 60, IBHP 1435, FBHP - failed to register.

DST #2 - 3742-3749 Shut in 15 min., open 1 hr., shut in 15 min., recovered 15^{ft} mud. No pressures.

DST #3 - 3749-3769 Shut in 15 min., open 1 hr., shut in 15 min., recovered 24^{ft} mud. No pressures.

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1957

BEARDMORE DRILLING COMPANY

BY

Richard C. Beardmore

Subscribed and sworn to before me this 28th day of March, 1957.

CONSULING DIVISION
Wichita, Kansas

Leonard P. Tolle

Leonard P. Tolle-Notary Public

My Commission Expires:
January 28, 1960

PLUGGING
FILE SEC. 22 T. 29 R. 1W
BOOK PAGE 1 LINE 43