

15-173-19029-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

9


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

SEDGWICK County, Sec. 22 Twp 29S Rge. (X) 1 (W)

Location as "NE/CNW/SW" or footage from lines NW NE NE
Lease Owner I. O. MILLER
Lease Name POEHNER Well No. 1
Office Address 619 BROWN BLDG., WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 5-27-64 19 64
Application for plugging filed (PHONE 5-27-64) 6-1 19 64
Application for plugging approved 5-27 19 64
Plugging commenced 5-27 19 64
Plugging completed 5-27-64 19 64
Reason for abandonment of well or producing formation 5-27 64

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well PAUL TURPIN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3765 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	345	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILL HOLE WITH HEAVY MUD TO 240 FEET. SET FIRST PLUG WITH 1/2 SACK HULLS AND 20 SACKS CEMENT. FILL HOLE WITH HEAVY MUD TO 30 FEET. SET SECOND PLUG WITH 1/2 SACK HULLS AND 8 SACKS CEMENT. PLUG RAT HOLE WITH 2 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

JUN 2 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES INC.
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. E. Hall*

514 ORPHEUM BLDG., WICHITA, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of JUNE, 1964

My commission expires OCTOBER 2, 1967

Vira A. McKenzie
VIRA A. MCKENZIE, Notary Public.

R

GABBERT-JONES INC.
 WICHITA, KANSAS
 DRILLERS WELL LOG

POEHNER #1
 NW NE NE SECTION 22-29S-1W
 SEDGWICK COUNTY, KANSAS

COMMENCED: MAY 19, 1964
 COMPLETED: MAY 27, 1964

OPERATOR - I. O. MILLER OIL Co.

DEPTH		FORMATION	REMARKS
FROM	TO		
0	240	SAND & SHALE	
240	265	SHALE & SHELLS	
265	345	ANHYDRITE	RAN 17 JOINTS 8-5/8" CASING, SET @ 345' W/ 300 SACKS CEMENT
345	2490	LIME & SHALE	
2490	2620	SAND	
2620	2835	LIME & SHALE	
2835	3000	LIME	
3000	3370	SHALE & LIME	
3370	3483	LIME	
3483	3764	LIME & SHALE	
3764	3765	LIME	
3765	TD		DRY & ABANDONED

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN NW NE NE SECTION 22-29S-1W, SEDGWICK COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE ON THIS 2ND DAY OF JUNE, 1964, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Vera A. McKenzie
 VERA A. MCKENZIE, NOTARY PUBLIC

My Commission Expires October 2, 1967

RECEIVED
 STATE CORPORATION COMMISSION

JUN 2 1964

CONSERVATION DIVISION
 Wichita, Kansas