

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Sedgwick County. Sec. 21 Twp. 29 Rge. (E)-1 (W)

Location as "NE/CNWSWK" or footage from lines C SE SE

Lease Owner Aylward Drilling Company

Lease Name Luckner Well No. 1

Office Address 909 1st Nat'l Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 23 1964

Application for plugging filed April 23 1964

Application for plugging approved April 23 1964


Plugging commenced April 23 1964

Plugging completed April 23 1964

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Paul Turpin

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3825 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	348	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole to 200 feet with 40 vis mud.  
Set plug at 200 with 1/2 sack hulls and 15 sacks cement through drill pipe. Mudded hole to 30 feet.  
Set plug at 30 feet with 1/4 sack hulls and 8 sacks cement.  
Capped rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 21 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company tools

Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Charles D. Williams (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles D. Williams

909 1st Nat'l Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 1964

My commission expires December 11, 1965

Duane Jessup  
DUANE JESSUP Notary Public.



LUCKNER #1

Casing Record: 8 5/8" - 348'  
 Company: Aylward Drilling Company  
 Contractor: Aylward Drilling Company  
 Commenced: April 10, 1964  
 Completed: April 23, 1964  
 Location: C SE SE  
 Sec. 22-29-1W  
 Sedgwick County  
 Kansas  
 Elevation: 1273 R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	60	Set 8 5/8" surface pipe @ 348'
Lime & Shale	60	260	w/300 sacks cement
Lime	260	565	
Lime & Shale	565	1695	Geological Tops:
Shale	1695	1910	
Shale & Lime	1910	2535	Stalnaker 2545
Shale	2535	2700	Kansas City 2867
Shale & Lime	2700	2867	Base Kansas City 3075
Lime	2867	3295	Mississippi 3433
Lime & Shale	3295	3490	Kinderhook 3766
Lime	3490	3825 T.D.	Simpson 3820

No D.S.T.  
 No Log

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 21 1964

CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

*Charles D. Williams*

Subscribed and sworn to before me this 29th day of April, 1964

*Duane Jessup*  
 DUANE JESSUP Notary Public

My commission expires December 11, 1965