

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-191-21,069-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 6/99

WELL OPERATOR Bear Petroleum, Inc. KCC LICENSE # 4419
(owner/company name) (operator's)

ADDRESS Box 438 CITY Haysville

STATE KS ZIP CODE 67060 CONTACT PHONE # (316) 524-1225

LEASE Russell WELL# 1 SEC. 35 T. 30 R. 2 (East/West)

NE - SE - NW SPOT LOCATION/0000 COUNTY Sumner

3630 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2970 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 453 CEMENTED WITH 300 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 3814 CEMENTED WITH 225 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3772-76

ELEVATION 1335 T.D. 3815 PBDT 3785 ANHYDRITE DEPTH NA
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Dump sand from TD to 3722' and dump bail 4 sax cement.

Shoot and pull pipe, run tubing to 453', spot 35 sax, pull tubing to 250',

circulate cement to surface, and pull tubing.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dick Schrenmer PHONE# (316) 524-1225

ADDRESS 438 City/State Haysville, KS 67060

PLUGGING CONTRACTOR Gressel Oil Field Service, Inc. KCC LICENSE # 3004

(company name) (contractor's)

ADDRESS Box 607, Burrton, KS 67020 PHONE # (316) 463-5161

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) unknown

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9-16-98 AUTHORIZED OPERATOR/AGENT: [Signature]

(signature) R.A. Schrenmer

RECEIVED
KANSAS
CORPORATION
COMMISSION
6/99
4-8-98

K. G. S. LIBRARY

State Geological Survey
WICHITA, BRANCH

L O G

Well Name: #1 Russell

Operator: Wheatland Oil & Gas, Inc.

Spud Date: 8-3--80

Contractor: Ramco Drilling Corp.

Completion Date: 9-6-80

Casing: 8 5/8" @ 453' w/300 sx.
4 1/2" @ 3814' w/225 sx.

Location: NE SE NW Sec. 35-30S-2W
Sumner County, Kansas

1335KB
logged

FORMATION

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface soils & Shale	0	120
Sand & Shale	120	1142
Shale	1142	3090
Shale & Lime	3090	3480
Lime & Shale	3480	3603
Shale & Lime	3603	3815
Rotary Total Depth	3815	

RECEIVED
RAMCO DRILLING CORP. CO.,
1980 SEP 18 A 11:29

STATE OF KANSAS, COUNTY OF BUTLER: ss

I certify that the above information is true and correct to the best of my knowledge.


THE RAMCO DRILLING CORPORATION

J. V. Crawford
J. V. Crawford, Vice President

Subscribed and sworn to before me on this 25th day of Sept., 1980

Sandra Kay May
Sandra Kay May Notary Public

My appt. exp:

	SANDRA KAY MAY NOTARY PUBLIC Butler County, Kansas My Appt. Exp. 6-30-84
---	---



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltsam, Commissioner Cynthia L. Claus, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

September 18, 1998

Bear Petroleum, Inc.
PO Box 438
Haysville, Ks. 67060

Russell #1
API 15-19121069
NE SE NW
Sec. 35-30S-2W
Sumner County

Dear Dick Schremmer,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #2
130 S. Market Room 2125
Wichita KS 67202-3208
(316) 337-6231