

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

RECEIVED
FORM CP-1 (3/92)
JUN 09 2003

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 1511920798-0000 (Identifier number of this well). This must be like **KCC WICHITA**
wells drilled since 1967; if no API# was issued, indicate spud or completion date. *8/03*

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)
ADDRESS 701 S. TAYLOR, STE 400 CITY AMARILLO
STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600

LEASE SENSENICH WELL# A-1 SEC. 24 T. 32 R. 30 (xxxx/West)
- - - NE SPOT LOCATION/QQQQ COUNTY MEADE

990 FEET (in exact footage) FROM X/N (circle one) LINE OF SECTION (NOT Lease Line)
1980 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8-5/8 SET AT 1612 CEMENTED WITH 200 SACKS
PRODUCTION CASING SIZE 4-1/2 SET AT 5969 CEMENTED WITH ETOC @ 4575 SACKS
CIBP: 5660, 5850.

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: PERFS: 5870-5876, 5664-5672, 5612-5646

ELEVATION 2726 / _____ T.D. 6127 PBDT 5660 ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING SPOT 2 SXS HULLS AND 10 SXS CMT FROM 5660 TO 5515. SHOOT
OFF 4-1/2 CSG AT FREE POINT. SPOT 50 SXS CMT FROM 1670 TO 1520. SPOT 40 SXS CMT FROM
700 TO 580. SPOT 15 SXS CMT FROM 40 TO 4. CUT OFF AND CAP 8-5/8 CSG 4 BELOW GL.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES
If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAVID RELEFORD PHONE# (620) 482-1000
ADDRESS 1707 W 2ND City/State LIBERAL, KS 67901

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)
ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515 *1/04*

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT
DATE: 6/5/2003 AUTHORIZED OPERATOR/AGENT: Craig R. Walters
CRAIG R. WALTERS, P.E. (Signature)
DIVISION PRODUCTION ENGINEER



CORPORATION COMMISSION

Kathleen Sebellus, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation
1201 Lake Robbins Drive
The Woodlands, TX 77380

June 10, 2003

Re: SENSENICH A #1
API 15-119-20798-00-00
S2NWNE 24-32S-30W, 990 FNL 1980 FEL
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888