

STATE OF KANSAS
STATE CORPORATION COMMISSION

Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

NOTICE: TYPE OR PRINT
Fill out completely
and return to Cons. Div.
office within 30 days

API NUMBER 15-129-21421 - 0000

LEASE NAME PAYNE "A"

WELL NUMBER 1

4620 Ft. from S Section Line

810 Ft. from E Section Line

SEC. 7 TWP. 33 RGE 41 (X) or (W)

COUNTY MORTON

Date Well Completed NOT APPLICABLE

Plugging Commenced 2-2-96

Plugging Completed 2-2-96

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-2-96 (date)

by STEVE MIDDLETON (KCC District Agent's Name).

Is AC0-1 filed? YES (ATTACHED) If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 3200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	564	NONE

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

TIH W/DRILLPIPE TO 1550' SPOT 50 SX 60/40 POZMIX W/6% GEL FROM 1550' TO 1300' TOH TO 590' PUMP 50 SKS PLUG FROM 590' TO 330' TOH TO 40' PUMP 10 SX FROM 40' TO 0' 15 SX IN RATHOLE AND 10 SX IN MOUSEHOLE. HEAVY DRILLING MUD PUMPED BETWEEN EACH PLUG. CUT OFF & CAP 8-5/8 CSG 3' BELOW GL. PERMANENTLY INSCRIBE WELL NAME AND DATE PLUGGED ON CAP. KCC REP: STEVE MIDDLETON.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor: BIG "A" DRILLING INC. License No. 31572

Address P O BOX 1856, LIBERAL, KANSAS 67905-1856

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

FEB 12 1996

STATE OF KANSAS COUNTY OF SEWARD, ss.

2-12-96

CONSERVATION DIVISION

DAVID W. KAPPLE

(Employee of Operator) or (xxxxxxx) of above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 7th day of February, 19 96

L. MARC HARVEY
Notary Public - State of Kansas
My Appt. Expires 6-12-99

L. Marc Harvey
Notary Public

My Commission Expires _____