


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Morton County. Sec. 8 Twp. 33S Rge. (E) 41 (W)
Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner Amarillo Oil Company
Lease Name PATSY MONTGOMERY Well No. 1
Office Address P. O. Box 151, Amarillo, Texas 79105
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-23-70 19 70
Application for plugging filed 2-26-70 19 70
Application for plugging approved Verbally by 2-23 19 70
Plugging commenced 2-23 19 70
Plugging completed 2-24 19 70
Reason for abandonment of well or producing formation Well was Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production New Well 19 70
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott, Bubleette, Kansas
Producing formation None Depth to top Bottom Total Depth of Well 5065 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
No producing formations				8-5/8	1477	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 35 Sx Cement plug 900 - 1000'
Set 15 Sx Cement plug 0 - 45'
Set 5 Sx Cement plug Rat Hole
Set 5 Sx Cement plug Mouse Hole
Left Hole filled with 90# Mud.

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor The Halliburton Co. and Lohman-Johnson Drilling Co.
Address Elkhart, Kansas Oklahoma City, Oklahoma

STATE OF Texas COUNTY OF Potter, ss.
J. A. Tipton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Po Box 151, Amarillo Texas 79105
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of February, 19 70

My commission expires June 1, 1970
Florence Small
FLORENE SMALL Notary Public.

WELL LOG

Company: Amarillo Oil Company

Sec. 8 T. 33-S R. 41-W

Farm: Patsy Montgomery

No.: 1

Loc.: C SW SW

Total Depth: 5065

County: Morton

Comm.: 2-12-70

Comp.: 2-23-70

Contractor: Lohman - Johnson Drilling Company

Casing: 8-5/8" Csg Cemented @ 1477

Elevation: 3430 K.B.

Production: D & A

"Figures Indicate Bottom of Formations"

0 - 700	Surface sd & shale
700 - 1000	Red sh, Anhy, & sd.
1000 - 1150	Anhydrite
1150 - 1450	Red Sh & Anhydrite
1450 - 1500	Anhydrite
1500 - 2600	Red Sh & Sd.
2600 - 2816	Limestone & Red Sh. Waubausee - 2816'
2816 - 3009	Limestone & Sh. Topeka - 3009'
3009 - 3386	Limestone Lansing - 3386'
3386 - 3740	Limestone & Sh.
3740 - 3900	Sh & Sandstone
3900 - 4120	Limestone & Sh.
4120 - 4330	Sh & Limestone
4330 - 4420	Sd & Siltstone
4420 - 4640	Limestone & Sh.
4640 - 4740	Sandstone & Sh.
4740 - 4862	Limestone & Sh. Morrow - 4862'
4862 - 4984	Shale
4984 - 4995	Sand
4995 - 5065	Shale
5065 -	Total Depth

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1970
CONSERVATION DIVISION
Wichita, Kansas

State of Texas)
County of Potter) ss.

I, J. A. Tipton of AMARILLO OIL COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the
Patsy Montgomery #1 well.

J. A. Tipton

Subscribed and sworn to before me this 13th day of March, 19 70

My Commission Expires: 6-1-71

Mary Coffey

Notary Public
Potter County, Texas