

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stevens County, Sec. 29 Twp. 33 Rge. 36 XX/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C-SE 1/4


Lease Owner Northern Pump Co.
Lease Name Carpenter Well No. 3
Office Address Box 937, Garden City, Ks. 67846
Character of Well (Completed as Oil, Gas or Dry Hole)
Gas

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 3-22-82 19
Plugging commenced 3-24-82 19
Plugging completed 3-25-82 19

Reason for abandonment of well or producing formation
Drilled replacement Well
If a producing well is abandoned, date of last production
Nov. 1962 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Thomas
Producing formation Hugoton Depth to top 2632 Bottom 2785 Total Depth of Well 2785
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				10 3/4"	664	0'
Production				7"	2632	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pumped 50 sks. cement to 2400' - Shut in over night
Put bridge & 40 sks. cement 764' to 564'

Displaced w/mud to 60'

Put bridge & 10 sks. cement 60' to 0'

Cut off 4', below ground level

RECEIVED
STATE CORPORATION COMMISSION
APR - 9 1982
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Nedwest Casing Pulling Service
Permit # 766

STATE OF Kansas COUNTY OF Haskell, ss.
I, Edgar J. Eves (employee/owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

Edgar J. Eves
Box 4, Sublette, Ks. 67877

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of April, 19 82

Sandra L. Eves

Notary Public.

My commission expires 12-6-84



15-189-00392-0000

Source: Log from R. E. L.

Well: Carpenter #3

Location: 29-33-36 S 4

Contractor:

Company:

Ruhn Bros.

County: Stevens County, Ks.

Completed:

Natural Open Flow: 2,241,000

Orig. Shut-In Pressure:

Elevation: 3,073.5'

From To

Formation

175 - Sand

175 - Hard Band

236 - Sand & Gravel

590 - Hard Band of Clay

1159 - Red Bed - Set 660' to 3/4" casing

1210 - Red Bed & Shells

1210 - Shale & Shells

1750 - Sticky Shale & Anhydrite

1802 - Anhydrite & Shale breaks

1918 - Shale & Shells

1980 - Anhydrite & Shell breaks

2000 - Broken Anhydrite

2082 - Anhydrite & Shale Breaks

2290 - Anhydrite

2505 - Anhydrite

2505 - Anhydrite & Sticky Shale

2552 - Blue Shale

2567 - Anhydrite

2586 - Anhydrite

2594 - Shale

2600 - Bottomite - Set 7" O.D. at 2685'

2605 - Grey & Red Shale

2655 - Broken Grey Lims

2660 - Broken Lims Gyp & Shale

2665 - Hard Grey Lims

2685 - Broken Lims & Shale

2695 - Grey Sandy Lims

2725 - Grey Sandy Lims

2735 - Broken Lims

2762 - Grey Lims

2767 - Grey Shale

2772 - Red Shale

2803 - Grey Lims

2803 - Grey Shale

2845 - Brown Shale

2870 - Grey Lims

Plugged back to 2805.

Gas Log

First show of Gas 2662 - 2665

Increase in Gas 2690 - 2695

Increase in Gas 2750 - 2755

Increase in Gas 2794 - 2805

Acidizing Record

Acidized with 2,000 Gal. No open flow taken
Acidized with 9,000 Gal. Open flow 14,259,000

31-11
32-1
33-1
34-1
35-1
36-1
37-1
38-1
39-1
40-1
41-1
42-1
43-1
44-1
45-1
46-1
47-1
48-1
49-1
50-1
51-1
52-1
53-1
54-1
55-1
56-1
57-1
58-1
59-1
60-1
61-1
62-1
63-1
64-1
65-1
66-1
67-1
68-1
69-1
70-1
71-1
72-1
73-1
74-1
75-1
76-1
77-1
78-1
79-1
80-1
81-1
82-1
83-1
84-1
85-1
86-1
87-1
88-1
89-1
90-1
91-1
92-1
93-1
94-1
95-1
96-1
97-1
98-1
99-1
100-1

no flow on this

RECEIVED
STATE CONSERVATION COMMISSION
MAR 11 1982
WICHITA, KANSAS
CONSERVATION DIVISION