

LEASE NAME W.I. Paden #1 Unit

WELL NUMBER 2

1320 Ft. from S Section Line

1320 Ft. from ^W Section Line

SEC. 33 TWP. 33 RGE. 36 (E) or (W)

COUNTY Stevens

Date Well Completed 1-6-85

Plugging Commenced 11-26-01

Plugging Completed 11-26-01

CONSERVATION DIVISION
WICHITA, KS

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Exxon Mobil Corporation

ADDRESS P.O. Box 4358 Houston, TX 77210-4358

PHONE (713) 431-1828 OPERATORS LICENSE NO. 5208

Character of Well GAS

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 11-26-01 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? —

Producing Formation Chase Depth to Top 2802 Bottom 2812 T.D. 3203

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 3/8	709	—
				5 1/2	3203	—

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each so Mixed 2 5x hulls & 25 5x cmt. to plug perfs from 2812 to 2612, mud to 1700, 25 5x cmt 1700 to 1500, mud to 760, 95 5x 760 to 0. Mixed 5 5x down annulus & pressure up to 500. Cut off 8 3/8 & 5 1/2 & capped 8 3/8 3 ft. below G/L

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EXXON MOBIL CORPORATION

STATE OF KANSAS COUNTY OF STEVENS, ss.

RICHARD LEWIS (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) RB Lewis

(Address) PO Box 400 HOUSTON KS

SUBSCRIBED AND SWORN TO before me this 30th day of November, 2001

Delores M. Gleming
Notary Public

My Commission Expires: 8-11-2002

OR