

KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-20795-00-00

LEASE NAME Fulkerson Unit 1

WELL NUMBER 2

1250 Ft. from S Section Line

4030 Ft. from E Section Line

SEC. 36 TWP. 33 RGE. 36 or (W)

COUNTY Stevens

Date Well Completed 1984

Plugging Commenced 12-6-01

Plugging Completed 12-6-01

RECEIVED  
1-18-02 JAN 18 2002 ply

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

LEASE OPERATOR Exxon Mobil Corporation

ADDRESS P.O. Box 4358, Houston, TX 77210

PHONE (713) 431-1828 OPERATORS LICENSE NO. 5208

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-6-01 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation 3020 Depth to Top 3042 Bottom T.D. 3200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	795	-
				5 1/2	3200	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each so  
Mixed 3 sx hulls & 25 sx cmt. to plug perfs from 3020 to 2820, mud to 1700, mixed 25 sx cmt. 1700 to 1500, mud to 800, 90 sx cmt. 800 to 0. Mixed 18 sx cmt. down 8 5/8-5 1/2 annulus from 108 to 0 & pres. up. Cut off 8 5/8 & 5 1/2 & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EXXON MOBIL

STATE OF KANSAS COUNTY OF STEVENS, ss.

RICHARD B. Lewis (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) R. B. Lewis

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 9th day of January, 2002  
Harold M. Fleming  
Notary Public

My Commission Expires: 8-11-2002