

NOV 13 2002

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CONSERVATION DIVISION
WICHITA, KS

LEASE OPERATOR ExxonMobil Production Corp.

ADDRESS PO Box 4358 Houston TX 77210

PHONE (713) 431 1828 OPERATORS LICENSE NO. 5208

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-22-02 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation MORROW Depth to Top 6104 Bottom 6144 T.D. 6446

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				<u>9 5/8</u>	<u>767</u>	
				<u>5 1/2</u>	<u>6430</u>	<u>1010</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each section.
CIBP + 2 SX 5985 to 5965 CIBP + 2 SX 2952 to 2932 5 1/2 stuck @ 1100
cut loose @ 1010 Pulled to 800 Circ. hole w/mud 70 SX 800 to 610
15 SX 40 to 0 Cut off & capped 9 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EXXON MOBIL PRODUCTION COMPANY

STATE OF KANSAS COUNTY OF STEVENS, ss.

RICHARD B. LEWIS (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) R B Lewis

(Address) PO Box 400 HUGOTON KS 67951

SUBSCRIBED AND SWORN TO before me this 4th day of November 2002



Janet K Lewis
Notary Public

My Commission Expires: 7/25/2006