

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-189-21047-00-00

LEASE NAME Rhoda Smith

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER 1

SPOT LOCATION NE-NE

LEASE OPERATOR BELCO ENERGY CORPORATION

SEC. 9 TWP 33 RGE. 35 (E) OR (W)

ADDRESS 8908 S. Yale/Suite 340 Tulsa, Okla 74137-3522

COUNTY Stevens

PHONE # (918) 481-6020

OPERATORS LICENSE NO. 31269

DATE WELL COMPLETED 6-2-87

PLUGGING COMMENCED 6-21-01

CHARACTER OF WELL oil
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMPLETED 6-26-01

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACG-1 FILED? yes IF NOT, IS WELL LOG ATTACHED? yes

PRODUCING FORMATION MORROW DEPTH TO TOP _____ BOTTOM T.D. 6400

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>MORROW</u>	<u>Oil & Gas</u>	<u>6012</u>	<u>6032</u>	<u>8 5/8</u>	<u>1732</u>	<u>-0-</u>
				<u>5 1/2</u>	<u>6400</u>	<u>-1863-</u>
				<u>2 7/8</u>	<u>6050</u>	<u>-5910-</u>


DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Cut off tubing @5910'. Circulated hole w/10 bbl. mud. Set CIBP @5910' w/2 sx. cement on top. Cut off 5 1/2 casing @1863'. Pump 50 sx. cement 1750' to 1600' displaced w/mud. Pumped 40 sx. cement 550 to 450'. Displaced w/mud. Pump 10 sx. 40' to surface circulated.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR JERRY DUNKIN WELL SERVICES, INC. LICENSE NO. 8733
ADDRESS P.O. Box 389 Enid, Oklahoma 73702

STATE OF _____ COUNTY OF _____, SS.

PAUL DAVIS (EMPLOYEE OF OPERATOR) OR
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND
CORRECT, SO HELP ME GOD.



(SIGNATURE) Paul Davis

(ADDRESS) 8908 S YALE
TULSA OK 74137

SUBSCRIBED AND SWORN TO BEFORE ME THIS 16 DAY OF AUGUST, 2001

Darryl D. [Signature]
NOTARY PUBLIC

MY COMMISSION EXPIRES: 1-23-05

RECEIVED
ST. CORPORATION COMMISSION

FORM CP-4
REVISED 06-83

AUG 20 2001

Conservation Division
Wichita, Kansas

OR