

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Stevens SEC. 12 TWP. 33S RGE. 35 NE/W  
Location as in quarters or footage from lines:  
NE NE NE, 330' from N & E lines of NE/4


Lease Owner ARCO Oil and Gas Company  
A Division of Atlantic Richfield Company

Lease Name Wallace Well No. 3

Office Address P. O. Box 521, Tulsa, Oklahoma 74102

Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole

Date Well Completed 12-25-83

Application for plugging filed Verbal

Plugging commenced 12-24-83

Plugging completed 12-25-83

Reason for abandonment of well or producing formation Dry hole

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation Dry Hole Depth to top \_\_\_\_\_ bottom T.D. 6480'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Chase	Gas	2744'	3000'	8-5/8"	1709'	None
Council Grove	"	3000	4174			
Morrow	Water	5631	5934			
Chester		5934	6172			
Basal Chester Sand	Oil-Water	6136	6172			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 4 feet to 1760 feet for each plug set.

GIH with drill pipe to bottom of surface casing, circulate hole w/9# drilling mud. Set cement plugs as follows: 1640' to 1760' w/50 sks 60/40 poz w/2% gel & 3% cc, 700' to 800' w/50 sks 60/40 poz w/2% gel & 3% cc, 4' to 40' w/10 sks 60/40 poz w/2% gel & 3% cc - filled rat hole w/15 sks and mouse hole w/10 sks of same.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Johnson Drilling Company, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss.  
G. L. Weger (~~employee of owner~~ or ~~owner or operator~~) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) *G. L. Weger*  
Box 521, Tulsa, Oklahoma 74102  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of January, 19 84

*Chairs Mallory*  
Notary Public.

My Commission expires: July 22, 1986

RECEIVED  
STATE CORPORATION COMMISSION  
1-11-84  
JAN 11 1984

CONSERVATION DIVISION  
Wichita, Kansas

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-189-20688-0000

NEL4, Sec. 12, T 33 S, R 35 W/8

330 feet from N/8 section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5398

Lease Name Wallace Well # 3

Operator: Arco Oil & Gas Co  
Name & Address: A Division of Atlantic Richfield  
PO Box 521 Tulsa Okla.  
74102

County Stevens

Well Total Depth 6480 feet 210.60

Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_

Surface Casing: Size 8 5/8 feet 1710

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Johnson Drlg License Number 7860

Address Liberal KS

Company to plug at: Hour: 8:00 pm Day: 24 Month: Dec Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Hapkins

(company name) Arco Oil & Gas (phone) \_\_\_\_\_

were: Heavy mud to 1710' cir. 50 sy cement at 1710' mud  
to 800' 50 sy cement mud to 40' solid bridge 8 5/8 plug 10 sy  
cement to surface. 15 sy cement in Rothels 10 sy cement in  
moose hole 60/40 pg 29 gal 39 cc

Signed J. M. Truf  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:00 am Day: 25 Month: Dec Year: 19 83

ACTUAL PLUGGING REPORT Same as Above

Remarks: Cemented by Halliburton

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

INVOICED

DATE 1-12-84

INV. NO. 9019 W

RECEIVED  
STATE CORPORATION COMMISSION

DEC 30 1983

CONSERVATION DIVISION  
Wichita, Kansas

Signed J. M. Truf  
(TECHNICIAN)