

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15 189 20,837 -0000

LEASE NAME Woods

WELL NUMBER 13

2586 Ft. from S Section Line

2338 Ft. from E Section Line

SEC. 12 TWP. 33 RGE. 35 COR. (W)

COUNTY Stevens

Date Well Completed 5-23-85

Plugging Commenced 5-27-85

Plugging Completed 5-29-85

LEASE OPERATOR ARCO Oil and Gas Company  
A Division of Atlantic Richfield Company

ADDRESS P. O. Box 521, Tulsa, Oklahoma 74102

PHONE# (918) 588-8200 OPERATORS LICENSE NO. 5398

Character of Well Dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Dry Hole Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 6600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
St Louis	Water	6422	52'	8-5/8"	1799'	0
Chester	" "	6219	26	5-1/2"	6599	1900'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIRP's set @ 6395' and 6185'. Cut 5-1/2" casing @ 1900' and pulled. Loaded hole w/9.8# mud, pumped 50 sk cement plug 1828' to 1700', pumped 40 sd cement plug 690' to 590' and set 10 sk top plug from 30' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton, Inc. License No. \_\_\_\_\_

Address Liberal, Kansas 67901

STATE OF Oklahoma COUNTY OF Tulsa, ss. CONSERVATION DIVISION

Carl W. Brown (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carl W. Brown

(Address) P. O. Box 521, Tulsa, Oklahoma

SUBSCRIBED AND SWORN TO before me this 4th day of June, 19 85

Maura Mallory  
Notary Public

My Commission Expires: July 22, 1986