

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-175-20684-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. *8/94*

WELL OPERATOR Anadarko Petroleum Corporation KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P. O. Box 351 CITY Liberal

STATE Kansas ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE Hitch Unit WELL# 3-1 SEC. 11 T. 33S R. 34 (East/West)

C - SW - SW - NW SPOT LOCATION/QQQQ COUNTY Seward

2310 FEET (in exact footage) FROM S/(N) (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E/(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1670' CEMENTED WITH 675 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 6399' CEMENTED WITH 210 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs: 6184-6214'

ELEVATION 2922 T.D. 6400 PSTD 6359 ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Pump 10,000 gal Injectrol-G + 100 sx Cl. H across perfs through cement retainer, 20 sx Cl. H at cutoff point, 35 sx Cl. H across surface shoe, and 15 sx Cl. H from 54-4'.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Previously submitted IS ACCO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING Jerry Ruttman

PHONE# (316) 624-6253

ADDRESS P. O. Box 351 City/State Liberal, Kansas 67905-0351

PLUGGING CONTRACTOR Sargent's and Horton Plugging, Inc. KCC LICENSE # 1151
(company name) (contractor)

ADDRESS Rt. 1 Box 49 BA, Tyrone, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8/4/94 AUTHORIZED OPERATOR/AGENT: David W. Kapple

(signature)

David W. Kapple, Division Production Engineer

STATE CORPORATION COMMISSION
RECEIVED
8-09-94
AUG 09 1994
CONSERVATION DIVISION
KANSAS

D



Kansas Corporation Commission

Joan Finney, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

August 15, 1994

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Hitch Unit #3-1
API 15-175-20,684
2310 FNL 330 FWL
Sec. 11-33S-34W
Seward County

Dear Jerry Ruttman,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760