

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE COPY IN CONSERVATION DIVISION
WICHITA, KS)

API # 15175213160000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Anadarko Petroleum Corporation KCC LICENSE # 4549 8/94
(owner/company name) (operator's)

ADDRESS P. O. Box 351 CITY Liberal

STATE Kansas ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE B & B Royalty "A" WELL# 3 SEC. 15 T. 33S R. 34 (East/West)

SPOT LOCATION/0000 COUNTY Seward

660 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1250 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL ___ GAS WELL ___ D&A X SWD/ENHR WELL ___ DOCKET# ___

CONDUCTOR CASING SIZE NA SET AT ___ CEMENTED WITH ___ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1634 CEMENTED WITH 750 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 6030 CEMENTED WITH 235 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5670-5674' (sq'zd); Cmt retainer @ 5666'; 5650-5658'

ELEVATION 2900 T.D. 6375' PSTD 5666' ANHYDRITE DEPTH ___
(G.L./K&K) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR ___ CASING LEAK ___ JUNK IN HOLE ___

PROPOSED METHOD OF PLUGGING Ld hole w/9 ppg mud & establish injection down 5 1/2" csg. Spot

20 sxs cmt @ 5666-5600', Cut 5 1/2" csg @ 4000' & salvage. Spot 35 sxs @ cut-lff point.

Spot 35 sxs from 1684-1584'. Spot 10 sxs in 8 5/8" from 34-4'. Cut off 8 5/8" 4' below GL & cap.

(If additional space is needed attach separate page) Restore location.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Previously Submitted IS ACO-1 FILED? Yes

If not explain why? ___

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry Ruttman PHONE# (316) 624-6253

ADDRESS P. O. Box 351 City/State Liberal, Kansas 67905-0351

PLUGGING CONTRACTOR Sargent & Horton Plugging, Inc. KCC LICENSE # 31151 1/94
(company name) (contractor's)

ADDRESS Rt 1 Box 49BA, Tyrone, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Upon Approval

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12/30/93 AUTHORIZED OPERATOR/AGENT: David Koppelo for
(signature)

J. L. Ashton, Division Production Manager

15-175-21316-0000

ANADARKO PETROLEUM CORPORATION

PHONE 316-624-6253 ◦ 2330 NORTH KANSAS AVE. ◦ P.O. BOX 351 ◦ LIBERAL, KANSAS 67905-0351

January 4, 1994



Kansas Corporation Commission
Conservation Division
200 Colorado Derby Building
Wichita, Kansas 67202

Attn: Priscilla Zadoka

Re: Plug and Abandonment
B & B Royalty "A" No. 3
Section 15-33S-34W
Seward County, Kansas
Shuck Field

Hayward "I" No. 3
Section 10-33S-40W
Morton County, Kansas
Stirrup Field

Dear Ms. Zadoka:

Enclosed in duplicate is the "Well Plugging Application" (KCC Form CP-1) submitted for your approval to plug and abandon the subject wells.

Upon approval of these applications, please notify Anadarko's Liberal office at the letterhead address so that operations may commence.

Very truly yours,

David Kappeler

J. L. Ashton
Division Production Manager
CLM-BJW/cs

Enclosures

cc: Well Files
Ken Lester - HGO
Manager Land Administration - HGO
Ellen Cobb - HGO
WI Owners
Sargent & Horton Plugging Inc.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 06 1994

CONSERVATION DIVISION
WICHITA, KS



Kansas Corporation Commission

Joan Finney, Governor Jim Robinson, Chairman F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 6, 1994

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

B & B Royalty "A" #3
API 15-175-21,316
660 FNL 1250 FEL
Sec.15-33S-34W
Seward County

Dear Jerry Ruttman,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760