

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-189-21,389 - 0000

LEASE NAME Nix "A"

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1-30

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 30 TWP. 33 SRGE. 35 or W

COUNTY Stevens

Date Well Completed 1-5-90

Plugging Commenced 7-12-90

Plugging Completed 7-12-90

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202

PHONE# 316 265-9697 OPERATORS LICENSE NO. 5003

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, Is well log attached? _____

Producing Formation Council Grove Depth to Top _____ Bottom T.D. @ 6650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|------|--------|--------|------------|
| | | 0 | 1740 | 8-5/8" | 1740' | None |
| | | | 3298 | 4-1/2" | 3298' | 1650' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ 2500'. Place 3 sx cement of top plug. Cut 4-1/2" casing @ 1650'. Circulate hole w/ gel. Place 50 sx plug @ 1650'. Place 40 sx plug @ 690'. Place top plug @ 40' to surface w/10 sx cement. Used 60-40 Pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Attica, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John Roger McCoy (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Roger McCoy

(Address) 110 S. Main, Suite 500
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 90

Lorna Leslie Hull
Notary Public

My Commission Expires: 1-11-92