

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-21959-0000

LEASE NAME G. P. Schweitzer

WELL NUMBER 35-2

3960 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 35 TWP. 33 SRGE. 35W (E) or (W)

COUNTY Stevens

Date Well Completed 10/7/95

Plugging Commenced 5/22/01

Plugging Completed 5/23/01

LEASE OPERATOR Texaco E&P, Inc.

ADDRESS 1109 Skelly Ave. Guymon, OK 73942

PHONE # 580 338-6820 OPERATORS LICENSE NO. 4742

Character of Well Gas

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/21/01 (date)

by Kevin Strube (KCC District Agent's Name)

is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Chase Depth to Top 2674 Bottom 2816 T.D. 2900 PBTD 2852

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chase	Gas	2674	2816	8 5/8"	617	-0-
				4 1/2"	2899	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

See Attached Daily Report

Name of Plugging Contractor H&K Plugging & Salvage License No. 31705

Address P.O. Box 2742 Pampa, TX 79066-2742

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texaco E&P, Inc. / Ken Austin

STATE OF Oklahoma COUNTY OF Texas, ss.

Texaco E&P Inc. / Ken Austin (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 1109 Skelly Ave. Guymon, OK 73942

SUBSCRIBED AND SWORN TO before me this 29th day of May, 20 01

My Commission Expires: 4/3/04
H. Dean Dicken Notary Public

RECEIVED

KANSAS CORPORATION COMMISSION

USE ONLY ONE SIDE OF EACH FORM

JUN 1 2001 Form CP-4
REVISED 05-88

CONSERVATION DIVISION

[Handwritten mark]

Holman Services

Well Plugging Specialist

Phone 806-665-2550 * Fax 806-665-2719
P O Box 2742 Pampa, Texas 79066-2742
Dennis Lee Holman

Texaso ESP, Inc.
Daily P&A Report
C.H. Schweitzer #2

5-22-01

MRO, pulled rods and tubing, pumped 40 barrels mud, set CIBP at 2624 feet with 2 sacks cement on top, pressured tested between 8 5/8 and 4 1/2 to 500# with 45 sacks cement, ran tubing to 1600 feet, circulated hole with mud, pumped 30 sacks cement at 1600 feet, pulled tubing to 640 feet, pumped 30 sacks cement, pulled tubing to 60 feet, pumped 10 sacks cement, rigged down and shut down for night Kevin Strobe/KCC on location

5-23-01

Rigged down, moved off location, dug out and cut off wall head, welded on steel ID plate and cleaned location.

15-189-21959-0000



Texaco North America Production
1109 Skelly Ave.
Guymon, OK 73942
580 338 6820

May 29, 2001

Kansas Corporation Commission
Conservation Division
130 South Market, RM 2078
Wichita, KS 67202

RE: G.H. Schweitzer #35-2
API # 15-189-21959
C / NE Sec. 35 T33S R35W
Stevens County Kansas

Gentlemen:

Attached is a Form CP-4 Well Plugging Record, for the subject well.

If you need anything more give me a call @ 580-338-6820.

Thanks,

H. Dean Dreher

H. Dean Dreher

Attachments