

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-217380000

LEASE NAME HITCH "H"

WELL NUMBER 2

500 Ft. from S Section Line

4580 Ft. from E Section Line

SEC. 8 TWP. 33 RGE 34 (E) or (W)

COUNTY SEWARD

Date Well Completed 7-30-98

Plugging Commenced 10-12-98

Plugging Completed 10-14-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-12-98 (date)

by MR. WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 6500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1589'	NONE
				5-1/2"	4384'	2001'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU PU, MIX & PUMP 3 SKS HULLS & 20 SKS CLASS 60/40 POZ CMT W/6% GEL TO PLUG PERFS FROM 4237 TO 4247'. PULL FREE POINT. BACK OFF 5 1/2" CSG @ 2001'. TOH WITH 5 1/2" CSG TO 1727'. PUMP 50 SKS CMT @ 1727'. TOH TO 600'. PUMP 40 SKS FROM 500-600'. TOH TO 43' & PUMP 10 SKS FROM 3-43'. CUT OFF AND CAP 8-5/8" 4' BELOW GL. PERMANENTLY INSCRIBE WELL NUMBER AND DATE PLUGGED ON CAP. RDMO. RESTORE LOCATION. KCC REP. MR. WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT 1, BOX 49 BA, TYRONE, OK. 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.


L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey 10-20-98
L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT
(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 20th day of October, 19 98

Shirley J Childers
Notary Public

My Commission Expires: 11/14/98



60270