

~~15-175-90230-0000~~

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
30 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA (DRILLED 1949)

LEASE NAME HITCH

WELL NUMBER 1-8

2840 Ft. from S Section Line

2542 Ft. from E Section Line

SEC. 8 TWP. 33 RGE 34 (E) or ( U )

COUNTY SEWARD

Date Well Completed 5/21/1949

Plugging Commenced 1/25/2000

Plugging Completed 1/25/2000

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/17/2000 (date)

by GARY WINTERS (KCC District Agent=s Name)

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation GLORIETTA Depth to Top 1200 Bottom 1315 T.D. 2740

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
GLORIETTA	SW	1200	1315	10 3/4"	607	0
				7"	2595	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. RELEASE PKR. TEST CSG TO 400#. PMP 5 SXS HULLS AND 50 SXS CMT @ 1345-1170. DISPLACE W/ 9PPG MUD. SPOT 40 SXS CMT @ 550-650. SPOT 15 SXS CMT @ 50 - 3. CUT OFF AND CAP CSG 3' BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287

Address PO BOX 1598, LIBERAL, KS 67905-1598 PHONE: (316) 624-3879

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young


SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 14th day of February, 2000

Shirley J. Childers  
Notary Public

My Commission Expires: \_\_\_\_\_



Form CR-4  
Revised 05-88

RECEIVED

STATE CORPORATION COMMISSION

FEB 16 2000

CONSERVATION DIVISION  
Wichita, Kansas