

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-175-20,684-0000

LEASE NAME Hitch Unit

WELL NUMBER 3-1

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 11 TWP. 33S RGE. 34 ~~XXX~~ or (W)

COUNTY Seward

Date Well Completed 7-3-83

Plugging Commenced 11-14-94

Plugging Completed 11-16-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, KS 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/16/94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation NA Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 6400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	1668	0'
				5 1/2"	6399	2823'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. MIRU csg pullers. Pull stretch in 5 1/2" csg and shot @ 2823'. Pmpd 25 sxs cmt @ 2800-2700'. Pull to 1700'. and pmpd 50 sxs from 1700-1600'. Pull to 700'. Pmpd 40 sxs cmt from 700-600'. Pull to 40' and pmp 10 sxs cmt from 40-0'. Lay dwn 2823' of 5 1/2" csg. Cut off and cap 3' below surface. State Witness: Glenn Barlow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49BA, Tyrone, Oklahoma 73951-9731 (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.


Leslie I. Barnes, Sr. Technical Assistant (Employee of Operator) or ~~Contractor~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leslie I. Barnes

(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 22nd day of November 1994

My Commission Expires:



Notary Public Cheryl Steers 11-29-94