

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20698 00-0
LEASE NAME HITCH UNIT
WELL NUMBER 8-1
4620 Ft. from S Section Line
4620 Ft. from 34 Section Line
SEC. 14 TWP. 33 RGE. 33 (X) or (W)
COUNTY SEWARD

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION
ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101
PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

RECEIVED

Date Well Completed 9-1-1983
Plugging Commenced 9-21-2003
Plugging Completed 9-22-2003

Character of Well INJECTION
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

APR 24 2003
KCC WICHITA

The plugging proposal was approved on 9-15-2003 (date)
by RICHARD LACEY (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation CHESTER Depth to Top 6125 Bottom 6227 T.D. 6340

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHESTER	OIL	6125	6227	8 5/8	1588	0
				5 1/2	6330	2533

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. PUMP 4 SXS HULLS AND 25 SXS CMT TO PLUG PERFS. SHOT OFF 5 1/2 CSG AT 2533. SPOT 50 SXS CMT FROM 1600 TO 1450. SPOT 40 SXS CMT FROM 600 TO 480. PLUG FROM 40 TO SURE. CUT OFF AND CAP 8 5/8 CSG BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.
CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 22 day of April, 2003



Commission Expires: 2/26/05

Lori Pearson
Notary Public