

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-189-21389-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR McCoy Petroleum Corporation OPERATOR'S LICENSE NO. 5003

ADDRESS 110 South Main - Suite 500 - Wichita, Ks 67202 PHONE # (316) 265-9697

LEASE (FARM) Nix "A" WELL NO. 1-30 WELL LOCATION C NW NW COUNTY Stevens

SEC. 30 TWP. 33S RGE. 35W or TOTAL DEPTH UTD 6649' PLUG BACK TD 3550'

Check One:

Top of cement @ 1670'

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1740' CEMENTED WITH 625 SACKS

CASING SIZE 4-1/2" SET AT 3298' CEMENTED WITH 325 SACKS

PERFORATED AT 2995-2998 (4 spf) 3008-3010 (4 spf) 3014-3024 (4 spf)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ 2550' +/- Place 3 sx cement on top w/dump

truck bailer. Cut off casing at approx. 1650'. Circulate hole w/ gel. Place 50 sk plug

@ 1650'; Place 40 sk plug @ 700'. Place top plug @ 40' to surface w/15 sk cement.

use 60-40 Pozmix, 6% gel. (If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Will Notify

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE # (316) 356-3510 or
(316) 532-5452

ADDRESS Kingman, Kansas

PLUGGING CONTRACTOR Hayes Well Service LICENSE NO. 5429

ADDRESS Attica, KS PHONE # (316) 254-7204

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: John Roger McCoy
(Operator or Agent)

DATE: 7-2-90

①

SUL 7-3-90 3 1990

6/41



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
JACK SHRIVER COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

**NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION**

July 16, 1990

McCoy Petroleum Corporation
110 South Main, Suite 500
Wichita, KS 67202

Nix "A" #1-30
C NW NW 30-33-35W
Stevens County, KS
API No. 15-189-21,389

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
Production Supervisor

District: #1, 304 W. McArtor
Dodge City, KS 67801