

To: 1090651

API NUMBER 15-129-21,421-0000

STATE CORPORATION COMMISSION

Wichita State Office Bldg. PLUGGING SECTION E/2 W/2 NE NE SEC. 7 T 33 S, R 41 W/E

130 S. Market, Room 2078
Wichita, KS 67202

2-2

660 feet from N/S section line

810 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Payne A Well # 1

Operator: Anadarko Petroleum Corp.

County Morton

Name & Address P.O. Box 351

Well Total Depth 3200 104.00 feet

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 564

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Big "A" Drilling License Number 31572

Address P.O. Box 1856, Liberal, KS 67905-1856

Company to plug at: Hour: Day: 2 Month: 2 Year: 1996

Plugging proposal received from Jim Barlow

(company name) Anadarko Petroleum Corp. (phone) 316-624-6253

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1550'

1st plug at 1550' with 50 sx cement, 2nd plug at 590' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: Day: 2 Month: 2 Year: 1996

ACTUAL PLUGGING REPORT 1st plug at 1550' with 50 sx cement,

2nd plug at 590' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. (if additional description is necessary, use BACK of this form.)

INVOICED (if not) observe this plugging.

Signed (TECHNICIAN)

DATE 2-20-96

WT. NO. 44862

EFFECTIVE DATE: 1-24-96

State of Kansas 15- NOTICE OF INTENTION TO DRILL 129-21,421-0000

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

DISTRICT # 1
SGA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 1-22-96
month day year

Spot E/2..W/2.NE.- ..NE. Sec ...7..Twp..33..S.Rg...41.. East West

OPERATOR: License # 4549
Name: ANADARKO PETROLEUM CORPORATION
Address: P.O. BOX 351
City/State/Zip: LIBERAL, KANSAS 67905-0351
Contact Person: JIM BARLOW
Phone: (316) 624-6253

660 feet from XXXX North line of Section
810 feet from East/ XXXX line of Section
IS SECTION X REGULAR IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)
County: MORTON
Lease Name: PAYNE "A" Well #: 1
Field Name: DUNKLE

CONTRACTOR: License #: 31572
Name: BIG "A" DRILLING

*Is this a Prorated/Spaced Field? yes X no
Target Formation(s): WABAUNSEE
Nearest lease or unit boundary: 660'
Ground Surface Elevation: 3420 feet MSL
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 180 (JK)
Depth to bottom of usable water: 480 (JK)
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 550'
Length of Conductor pipe required: NONE
Projected Total Depth: 3020'
Formation at Total Depth: WABAUNSEE
Water Source for Drilling Operations:
* X well X farm pond other

Well Drilled For: Well Class: Type Equipment:
Oil Enh Rec Infield X Mud Rotary
Gas Storage X Pool Ext. Air Rotary
OWWO Disposal Wildcat Cable
Seismic; # of Holes Other
Other
If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:
Exp. 7/19/96 AFFIDAVIT

*APPLY FOR PERMIT FROM DWR
Will Cores Be Taken? yes X no
If yes, proposed zone: 500' Alt. I Req.
*PRORATED AND SPACED IN CHASE GAS.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher 46-48-60
SPUD DATE 1/26/96 INIT. [Signature]
LENGTH SURFACE PLANNED 250'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2 @ 584 CONDUCTOR
ANHYDRITE T- B-1550 ELEVATION
TD 3200 FORMATION
DRILL PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Plug./Council @ Ft. W/ SX
Anhydrite Base @ 1550 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 590 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 17 SX MOUSE HOLE W/10 SX
WATER WELL SX (Irr. Well Pond)
TECHNICIAN SAM DATE 1-1-96 Hauling
TYPE OF CEMENT 624057
STARTING TIME (AM/PM) DATE
COMPLETION TIME (AM/PM) DATE 2-2-96
CEMENT COMPANY Akel