

1060848

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,800-0000

NW SE, SEC. 8, T 33 S, R 41 (W/S)

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029

1980 feet from S section line

Operator: Ladd Petroleum Corporation
Name & Address: P. O. Box 294
Liberal, KS 67901

1980 feet from E section line

Berryman-
Lease Name Richfield Well # 23-1

County Morton 165.10

Well Total Depth 5080 Morrow feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1480

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mustang Drilling & Exploration, Inc. License Number 5652

Address P. O. Box 1629, Great Bend, KS 67530

Company to plug at: Hour: 3:00 pm Day: 16 Month: April Year: 19 86

Plugging proposal received from Mike Campbell

(company name) Mustang (phone) 316-792-7323

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3408'
Anhydrite 1472-1489'

1st plug 50' below the base of the Hugoton and 50' above the Chase Group

2nd plug 30' below the base of the surface pipe with 40 sx cement

3rd plug at 600' with 30 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rathole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 8:15 pm Day: 16 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 5025' with 35 sx cement, 2nd plug at 2530' with 100

sx cement, 3rd plug at 1516' with 40 sx cement, 4th plug at 600' with 30 sx cement,

5th plug from 40' to surface with 10 sx cement, 6th plug to circulate rat hole with 10

sx cement.

STATE CORPORATION COMMISSION

APR 28 1986

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Dowell
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Paul A. Luthie (TECHNICIAN)

DATE APR 29 1986
INV. NO. 13587

4-16

NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

Starting Date April 14 1986
month day year

API Number 15- 129-20,800-0000

OPERATOR: License # 6029
Name Ladd Petroleum Corporation
Address P.O. Box 294
City/State/Zip Liberal, Kansas 67901
Contact Person Michael Brown
Phone 316-624-5227

NW SE 8 33 41 XX East
1980 Sec. Twp. S, Rg. West
1980 Ft. from South Line of Section
1980 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet
County Morton
Lease Name Berryman-Richfield Well # 23-1
Ground surface elevation 3408 feet MSL
Domestic well within 330 feet: —yes X no
Municipal well within one mile: —yes X no
Depth to bottom of fresh water 400
Depth to bottom of usable water 500
Surface pipe by Alternate: 1500' 8 5/8" 2
Surface pipe planned to be set 60' 20"
Conductor pipe required 5150
Projected Total Depth 5150 feet
Formation Morrow

CONTRACTOR: License #
Name unknown Mustang
City/State

Well Drilled For: Well Class: Type Equipment:
X Oil — SWD X Infield X Mud Rotary
— Gas — Inj — Pool, Ext. — Air Rotary
— OWWO — Expl — Wildcat — Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 3-27-86 Signature of Operator or Agent M. Brown Title District Superintendent

For KCC Use:
Conductor Pipe Required 500 feet; Minimum Surface Pipe Required 500 feet per Alt. ① ④
This Authorization Expires 7-28-86 Approved By 3-28-86

Speed - 4-7-86 -
8 5/8 1500' -
Start @ 2:30
Paul

NO
— East
— West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays). 50' Below Base Nug - 50' C. E. GPH - SACK ?

1st plug @ 1560 30' B Sp feet depth with 40 sxs of 60-40 Poz 6 1/2 -
2nd plug @ 600 O.K. feet depth with 30 sxs of 60-40 Poz
3rd plug @ 40 O.K. feet depth with 10 sxs of 60-40 Poz
4th plug @ feet depth with sxs of
5th plug @ feet depth with sxs of
(2) Rathole with 10 sxs (b) Mousehole with sxs

(50' below to 50' above chase group) D.G.

Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging.

PUSHER Mike Campbell
TD 5080 FORMATION Morrow
SURFACE PIPE 8 5/8 @ 1480
ANHYDRITE 1489 ELEVATION 3408
STARTING TIME & DATE 4-16-86 3:00 PM
COMPLETION TIME & DATE 4-16-86 8:15 PM
1st PLUG @ 50 2.5 FT. W/ 35 SX
2nd PLUG @ 25 30 FT. W/ 100 SX
3rd PLUG @ 15 16 FT. W/ 40 SX
4th PLUG @ 600 FT. W/ 30 SX
5th PLUG @ 40-0 W/ 10 SX
RAT HOLE CIRCULATED W/ 10 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Dowell prepared 6 1/2 w/ 6 1/2
TECHNICIAN Paul Smith saw all

APR 28 1986
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas