

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20805-00-01
Spot: CSW Sec/Twnshp/Rge: 33-33S-36W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease/Unit Name: WIPADEN Well Number: 1UT2
County: STEVENS Total Vertical Depth: 3203 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: PO BOX 4358
HOUSTON, TX 77210

Conductor Pipe: Size feet: 8.625 709 WITH 375 SX CMT
Surface Casing: Size 5.5 feet: 3203 WITH 500 SX CMT
Production: Size 5.5 feet: 3203 WITH 500 SX CMT
Liner: Size feet: 104.10

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/26/2001 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT ON BOTTOM. PUMP MUD TO 1700'. PUMP 25 SX CMT AT 1700'. PUMP WITH CMT FROM 730' TO SURFACE.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/26/2001 12:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2990'. PERFS AT 2802-12'. CIBP @ 2990'. PERFS BELOW 3042-70'. PUMPED DOWN 5 1/2" 200# HULLS & 25 SX CMT. MUD SPACER OF 21 BBLS TO 1700'. PUMPED 25 SX CMT AT 1700'. MUD SPACER 17.5 BBLS. RAN WIRE LINE TAGGED AT 760'. PUMPED 95 SX CMT FROM 760' TO 0'. PRESSURED UP TO 300#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 5 SX CMT. PRESSURED UP TO 500#.

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Kevin D. Strube

(TECHNICIAN)

RECEIVED

12-07-01
DEC 07 2001

INVOICED

KCC WICHITA

DATE 12-10-2001

NOV 30 2001

INV. NO. 2002061044

MP

[Signature]
Form CP-2/3