

2-19

To: 1 020296  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-189-20,802-0000

NE SE SW, SEC. 34, T 33 S, R 36 W/R  
1250 feet from S section line  
2920 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5208

Lease Name Morford #1 Unit Well # 2  
County Stevens 105.69

Operator: Mobil Oil Corporation  
Name & Address P.O. Box 5444  
Denver, CO 80217

Well Total Depth 3252 feet  
Conductor Pipe: Size          feet  
Surface Casing: Size 8 5/8 feet 680

Abandoned Oil Well          Gas Well X Input Well          SHD Well          D&A         

Other well as hereinafter indicated         

Plugging Contractor Mobil Oil Corporation License Number 5208  
Address 123 East 11th, Liberal, KS 67901

Company to plug at: Hour: 10:45 a.m. Day: 19 Month: 2 Year: 1990

Plugging proposal received from Tommy Romero

(company name) Mobil Oil Corporation (phone) 316-544-5500

were: 5 1/2" at 3252' PBSD 3197' Perfs at 3032-56' 5 1/2" Circ to Surf. w/485 sx.

1st plug set CIBP at 2950' with 2 sx cement, run tubing to 2928', load hole with heavy gel,

2nd plug pump 20 sx cement through tubing at 1800-1650',

3rd plug pull tubing to 730', circulate cement to surface.

Plugging Proposal Received by Glenn R. Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part          None         

Operations Completed: Hour: 12:30 p.m. Day: 19 Month: 2 Year: 1990

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2950' with 2 sx cement on top,  
ran tubing to 2928', load hole with heavy gel,

2nd plug pumped 20 sx cement through tubing at 1800-1650',

3rd plug pulled tubing to 730', circulated cement to surface.

Remarks: Used Class H cement by Halliburton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 3-2-90  
OBSERVE THIS PLUGGING.  
2-27-90

Signed Glenn R. Barlow  
(TECHNICIAN)

INV. NO. 27592  
2-19 APR 17 1990