

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20795-00-00
Spot: NENESWSW Sec/Twnshp/Rge: 36-33S-36W
1250 feet from S Section Line, 4030 feet from E Section Line
Lease/Unit Name: FULKERSON UNIT Well Number: 2
County: STEVENS Total Vertical Depth: 3200 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: PO BOX 4358
HOUSTON, TX 77210

Conductor Pipe: Size feet: 8 104 00
Surface Casing: Size 8.625 feet: 795 WITH 375 SX CMT
Production: Size 5.5 feet: 3200 WITH 600 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/06/2001 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: BOTTOM PLUG 300# HULLS & 25 SX CMT. MUD SPACER TO 1700'. PUMP 25 SX CMT. MUD SPACER TO 800 - 0'.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 12/06/2001 4:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PUMP 300# HULLS & 25 SX CMT. DISPLACE HOLE WITH MUD TO 1700'. PUMP 25 SX CMT FROM 1700-1500'. DISPLACE HOLE WITH MUD AT 800. PUMP 90 SX CMT FROM 800-0'. PUMP 18 SX CMT DOWN ANNULUS. PRESSURED UP TO 500#.

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin O Strube

(TECHNICIAN) DEC 07 2001

~~DEC 06 2001~~

Form CP-2/3

RECEIVED
DEC 14 2001
KCC WICHITA

INVOICED
DATE 12-19-01
TAX NO. 2002061072

NP