

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20782-00-00  
Spot: CNENENE Sec/Twnshp/Rge: 2-33S-35W  
330 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: DUANE HAMLIN Well Number: 1  
County: STEVENS Total Vertical Depth: 6455 feet

Operator License No.: 31269  
Op Name: BELCO ENERGY CORP.  
Address: 5735 PINELAND STE 300  
DALLAS, TX 75231

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 9.62 feet: 1900 600 SX CMT  
Production: Size 5.5 feet: 6455 WITH 300 SX CMT  
Liner: Size \_\_\_\_\_ feet: \$209.79

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/27/2001 9:00 AM  
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.  
Proposal Rcvd. from: TYLER Company: DUNKIN, JERRY, INC. Phone: (580) 237-6152

Proposed Plugging Method: CIBP @ 3400'. 1ST PLUG AT 1930' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/27/2001 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6426'. DV TOOL @ 3257'. PERFS AT 6094-6098'. CIBP @ 3460'. TAGGED CMT AT 3383'. PRESSURE TESTED CSG TO 500# FOR 30 MINUTES. DIDN'T BLEED OFF. LOAD HOLE WITH MUD. 1ST PLUG AT 1930' WITH 65 SX CMT. 2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 6 2001

CONSERVATION DIVISION

INVOICED

DATE 7-6-01

INV. NO. 2002060016

Remarks: USED COMMON CEMENT BY ALLIED. RECOVERED 2036' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland FIRTH  
(TECHNICIAN)

JUL 02 2001

Form CR-23