

1 020242

7-10

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-20,776-0000
SE NW NW, SEC. 3, T 33 S, R 35 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

4290 feet from S section line
4290 feet from E section line

Operator: Mobil Oil Corporation
Name & Address: P.O. Box 5444
Denver, CO 80217

Lease Name Becker #1 Unit Well # 2
County Stevens 104.00
Well Total Depth 3200 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 703

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mobil Oil Corporation License Number 5208
Address P.O. Box 5444, Denver, CO 80217

Company to plug at: Hour: 9 a.m. Day: 10 Month: 7 Year: 19 89

Plugging proposal received from Tommy Romero

(company name) Mobil Oil Corporation (phone) 316-544-5500

were: 5 1/2" at 3195' PBTB 3155' Perfs at 2998-3010'
1st plug set CIBP at 2900' with 2 sx cement on top,
2nd plug pump jel mud, pump 50 sx cement at 1799-1640' with tubing,
3rd plug space jel mud in hole, run 55 sx cement at 753', circulate to surface.

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:25 p.m. Day: 10 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2900' with 2 sx cement on top,

2nd plug pumped jel mud, pumped 50 sx cement at 1799-1640' with tubing, 50/50 Pozmix cement,
3rd plug spaced jel mud in hole, pumped 55 sx cement at 753', circulated to surface.
Used 65/35 light cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 50/50 Pozmix and 65/35 light cement by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

It is recommended that you observe this plugging.

Signed Glenn R. Barlow
(TECHNICIAN)

INVOICED
DATE 7-13-89
INV. NO. 25329

PLUG AND ABANDONMENT REPORT

BECKER 1-2
SE NW NW SEC. 03-33S35W
STEVENS COUNTY
AFE 9A-JX
PLUG AND ABANDONMENT

7/08/89 MOVER IN PATRICK WELL SERVICE AND RIG UP.

7/10/89 HALLIBURTON ON LOCATION. MIX UP 10 BLS OF GELL, PUMP DOWN HOLE VIA 5.5. WESTERN ATLAS ON LOCATION, RAN IN AND SET CIBP AT 2900'. RAN IN AND DUMPED TWO SX OF CMT ON PLUG. RAN IN 92 JTS OF 23/8 OPEN ENDED, PUMPED IN 26.5 BLL. OF GILL. PULLED 34 JTS. PLACE PLUG 50/50 FOZ MIX 1800-1640'. 16 SX. PULLED 5 JTS., PUMPED IN 21 BLS OF GELL. PULLED 29 JTS., TEG AT 744'— CIRCULATED HALLIBURTON LIGHT TO SURFACE, GOOD RETURN, TOTAL OF 61 SX'S. FULL REST OF TGB. OUT. WASHED UP AND RIG DOWN.

7/12/89 WENT OUT DUG AROUND WELL HEAD, CUT AND CAP OFF SURFACE AND PRODUCTION STRING. BACKFILLED AND DRESSED UP LOCATION. CAPPED APPROX. 5' BELOW GL.

FINAL REPORT
TOMMY ROMERO

CC: SUE MANN
RAY KELLEY, REGULATORY

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1989
CONSERVATION DIVISION
Wichita, Kansas

