

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20777-00-00  
Spot: SESENW Sec/Twnshp/Rge: 4-33S-35W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: HARMON GAS UNIT 1 Well Number: 2  
County: STEVENS Total Vertical Depth: 3200 feet

Operator License No.: 5208  
Operator Name: MOBIL OIL CORPORATION  
Address: PO BOX 4358  
HOUSTON, TX 77210

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 693  
Production: Size 5.5 feet: 3189  
Liner: Size \_\_\_\_\_ feet: 104.00

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/29/2000 10:30:00 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: JOHN RICE Company: MOBIL OIL CORP. Phone: (316) 544-5523

Proposed Plugging Method: BOTTOM PLUG PUMP 300# HULLS - 25 SX CMT - GEL SPACER TO 1700'. PUMP 25 SX CMT @ 1700'. GEL SPACER TO 720' & 720-0' WITH CMT. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/29/2000 11:30 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PERFS AT 2982-88. PUMP 3 SX HULLS & 25 SX CMT TO PLUG PERFS AT 2982-2782. LOAD WITH MUD TO 1700'. PUMP 25 SX CMT FROM 1700-1500. LOAD HOLE WITH MUD TO 1200'. MIX 135 SX CMT FROM 1200-0'. PUMP 50 SX DOWN 5 1/2 X 8 5/8 FROM 200' TO 0'. SHUT IN AT 500#. CEMENT AND CAPPED.

RECEIVED  
STATE CORPORATION COMMISSION  
10-11-00  
OCT 11 2000

Remarks: USED COMMON CMT BY SARGENTS. NO CASING RECOVERED.

CONSERVATION DIVISION  
Wichita, Kansas

Plugged through: CSG

District: 01

Signed \_\_\_\_\_  
(TECHNICIAN)

INVOICED

DATE 10/13/00

WELL NO. 2001060816

OCT 05 2000

MP

Form 2/2/00